EARTHWORK SCHEDULE

LOCATION	20200100 EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	20400800 FURNISHED EXCAVATION
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
I-55 MAINLINE					
NORTHBOUND					
STA 166+36 TO STA 173+06	520	416	232	184	0
SOUTHBOUND					
STA 153+42 TO STA 169+28	1135	908	759	149	141
TOTAL	1655	1324	991	333	141

SEEDING SCHEDULE

LOCATION	25000200 SEEDING, CL. 2	25000400 NITROGEN FERTILIZER NUTRIENT	25000500 PHOSPHORUS FERTILIZER NUTRIENT	25000600 POTASSIUM FERTILIZER NUTRIENT	25000700 AGRICULTURAL GROUND LIMESTONE
	ACRE	POUND	POUND	POUND	TON
I-55 MAINLINE					
NORTHBOUND					
STA 166+36 TO STA 173+06	0.4	36	36	36	0.8
SOUTHBOUND					
STA 153+42 TO STA 159+00	0.6	54	54	54	1.2
STA 161+00 TO STA 169+28	0.2	18	18	18	0.4
TOTAL	1.2	108	108	108	2.4

EROSION CONTROL SCHEDULE

LOCATION	25100115 MULCH, METHOD 2	25100635 HEAVY DUTY EROSION CONTROL BLANKET
	ACRE	SQ. YD.
I-55 MAINLINE		
NORTHBOUND		
STA 166+36 TO STA 171+00	0.4	
STA 171+00 TO STA 171+76		230
STA 172+60 TO STA 173+06		40
SOUTHBOUND		
STA 153+42 TO STA 159+00	0.6	
STA 159+00 TO STA 161+00		694
STA 161+00 TO STA 169+28	0.2	
TOTAL	1.2	964

FENCING SCHEDULE

LOCATION	66400405 CHAIN LINK FENCE 7'	Z0022800 FENCE REMOVAL
	LENGTH (FOOT)	LENGTH (FOOT)
I-55 MAINLINE		
SOUTHBOUND		
STA 159+62 TO STA 163+00	338	338
TOTAL	338	338

X2010505 - CLEARING(SPECIAL)

	(LSUM)
I-55 MAINLINE	
SOUTHBOUND	
STA 159+62 TO STA 163+00	1
TOTAL	1

* CLEARING LIMITS TO FENCE LINE

LOCATION	28000400 PERIMETER EROSION BARRIER
	FOOT
I-55 MAINLINE	
SOUTHBOUND	
STA 153+00 TO 170+00 LT	1700
NORTH BOUND	
STA 166+00 TO 174+00 RT	800
TOTAL	2500

FILE NAME = c:\pw_work\pwidot\sparksgw\d0326237\D672F90-sht-schedule.dgn	USER NAME = sparksgw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.8000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = Oct-17-2013 02:49:06PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET 3 OF 3 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(84-3)I-4	SANGAMON	56	10
		CONTRACT NO. 72F90		
		ILLINOIS FED. AID PROJECT		