URBAN

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FEDERAL 20% STATE	0005 50% STATE 50% CITY	0005 100% CITY	0021 100% STATE		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	217	148		69			
44000600	SIDEWALK REMOVAL	SQ FT	5153	3110		2043			
44003100	MEDIAN REMOVAL	SQ FT	301	301					
60260100	INLETS TO BE ADJUSTED	EACH	1	1					
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1	1					
60260600	INLETS TO BE ADJUSTED WITH NEW TYPE 4 FRAME AND GRATE	EACH	1	1					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	18	18					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	183	114		69			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5					
67100100	MOBILIZATION	L SUM	1	1					
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1					