CLARK COUNTY LOCATION 7

650 RD - 500 ST

SIGNS

BILL OF MATERIALS

| SIGN TYPES BY LOCATION | UNITS | | DIRECTION |
|--------------------------|-------|---|-----------|
| TURN (W1-1L) - 30" X 30" | EACH | 1 | WB |
| TURN (W1-1R) - 30" X 30" | EACH | 1 | EB |

| PAY ITEM DESCRIPTION | UNITS | |
|--------------------------------|-------|----|
| SIGN PANEL - TYPE 1 | SQ FT | 13 |
| TELESCOPING STEEL SIGN SUPPORT | FOOT | 33 |

CLARK COUNTY LOCATION 8

100 ST - 200 RD

SIGNS

| | | | | | | | | _ | | _ | _ | | |
|-----------------|-----|----|---|----|---|------|----|---|----|----|---|--------|--|
| BILL OF MATERIA | 1.8 | ΔI | Δ | 21 | ĸ | 1140 | ŊΊ | м | ١. | ΝН | • | RH | |

| SIGN TYPES BY LOCATION | UNITS | | DIRECTION |
|--------------------------|-------|---|-----------|
| TURN (W1-1L) - 30" X 30" | EACH | 1 | SB |

| PAY ITEM DESCRIPTION | UNITS | |
|--------------------------------|-------|----|
| SIGN PANEL - TYPE 1 | SQ FT | 7 |
| TELESCOPING STEEL SIGN SUPPORT | FOOT | 17 |

CLARK COUNTY LOCATION 9

400 RD - 300 ST

SIGNS

BILL OF MATERIALS

| SIGN TYPES BY LOCATION | UNITS | | DIRECTION |
|---|-------|---|-----------|
| REVERSE CURVE (W1-4L) - 30" X 30" | EACH | 1 | WB |
| REVERSE CURVE (W1-4R) - 30" X 30" | EACH | 1 | EB |
| ONE-DIRECTION LARGE ARROW (W1-6L) - 48" X 24" | EACH | 1 | SB |
| ONE-DIRECTION LARGE ARROW (W1-6R) - 48" X 24" | EACH | 1 | WB |

| PAY ITEM DESCRIPTION | UNITS | | |
|--------------------------------|-------|----|--|
| SIGN PANEL - TYPE 1 | SQ FT | 29 | |
| TELESCOPING STEEL SIGN SUPPORT | FOOT | 63 | |

| ſ | ILE NAME = | USER NAME = steffenmk | DESIGNED - | REVISED - | | BILL OF MATERIALS | | | | F.A. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | | |
|---|--|-------------------------------|------------|-----------|------------------------------|--------------------------|--------------------------|----|--------|------|------------------|----------|-----------------|--------------|--|--|
| | :\pw_work\pwidot\steffenmk\d0375948\D7 | 74656-sht-plan.dgn | DRAWN - | REVISED - | STATE OF ILLINOIS | | CLARK CO LOCATIONS 7 - 9 | | | | D7 SAFETY 2014-2 | VARIOUS | 61 | 30 | | |
| | | PLOT SCALE = 100.00000 '/ in. | CHECKED - | REVISED - | DEPARTMENT OF TRANSPORTATION | CLARK CU LUCATIONS 7 - 9 | | | | | | CONTRACT | NO. 7 | 4656 | | |
| | efault | PLOT DATE = 3/19/2014 | DATE - | REVISED - | | SCALE: | SHEET | OF | SHEETS | STA. | TO STA. | | ILLINOIS FED. A | ID PROJECT | | |