CLARK COUNTY LOCATION 10

400 RD - 420 ST

DIRECTION

PAY ITEM DESCRIPTIO

SIGN PANEL - TYPE 1

TELESCOPING STEEL SIGN SUPPORT

SIGN TYPES BY LOCATION	UNITS	
ν' Υ 30''	EACH	

SIGNS

CURVE (W1-2R) - 30" X 30"	EACH	1	ΕB
CHEVRON ALIGNMENT (W1-8L - YELLOW) - 18" X 24"	EACH	8	NB
CHEVRON ALIGNMENT (W1-8R - YELLOW) - 18" X 24"	EACH	8	EB

CLARK COUNTY LOCATION 11 CASTLE FINN RD - 2100 RD

PAY ITEM DESCRIPTION	UNITS		
SIGN PANEL - TYPE 1	SQ FT	13	
TELESCOPING STEEL SIGN SUPPORT	FOOT	33	

<u>SIGNS</u>

SIGN TYPES BY LOCATION	UNITS		DIRECTION
CURVE (W1-2L) - 30" X 30"	EACH	1	NB
CURVE (W1-2R) - 30" X 30"	EACH	1	SB

CLARK COUNTY LOCATION 12

CLARK SWITCHBOARD RD - 2000 RD

PAY ITEM DESCRIPTIO

SIGN PANEL - TYPE 1

TELESCOPING STEEL SIGN SUPPORT

<u>SIGNS</u>

SIGN TYPES BY LOCATION	UNITS		DIRECTION	
CHEVRON ALIGNMENT (W1-8L - YELLOW) - 18" X 24"	EACH	3	NB	
CHEVRON ALIGNMENT (W1-8R - YELLOW) - 18" X 24"	EACH	3	SB	

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -				RII		ATERIALS		F.A.	SECTION	COUNTY	TOTAL	SHEET
c:\pw_work\pwidot\steffenmk\d0375948\D7	74656-sht-plan.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS	CLARK CO LOCATIONS 10 – 12			D7 SAFETY 2014-2	VARIOUS	61	31				
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION			LANK CU	LUCATI	$\frac{1}{10} = \frac{1}{12}$				CONTRACT	Г NO. '	4656
Default	PLOT DATE = 3/19/2014	DATE -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.			ILLINOIS FED.							

BILL OF MATERIALS

ON	UNITS	
	SQ FT	55
	FOOT	137

BILL OF MATERIALS

BILL OF MATERIALS

ON	UNITS	
	SQ FT	18
	FOOT	90