## CLARK COUNTY LOCATION 19 MT. MORIAH RD - 1750 RD

**SIGNS** 

TURN (W1-1L) - 30" X 30"

TURN (W1-1R) - 30" X 30"

REVERSE CURVE (W1-4L) - 30" X 30"

# SIGN TYPES BY LOCATION UNITS DIRECTION (30" EACH 1 WB

2

EACH

### **BILL OF MATERIALS**

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	25
TELESCOPING STEEL SIGN SUPPORT	FOOT	66

# CLARK COUNTY LOCATION 20 ARMSTRONG RD

NB SB

**SIGNS** 

SIGN TYPES BY LOCATION	UNITS		DIRECTION
TURN (W1-1L) - 30" X 30"	EACH	3	NB SB
TURN (W1-1R) - 30" X 30"	EACH	3	EB WB

### **BILL OF MATERIALS**

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	38
TELESCOPING STEEL SIGN SUPPORT	FOOT	99

## **CLARK COUNTY LOCATION 21 FISHBACK RD - MT. MORIAH RD**

**SIGNS** 

SIGN TYPES BY LOCATION	UNITS		DIRECTION
WINDING ROAD (W1-5R) - 30" X 30"		1	ЕB

### **BILL OF MATERIALS**

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	7
TELESCOPING STEEL SIGN SUPPORT	FOOT	17

Default	PLOT DATE = 3/19/2014	DATE -	REVISED -	<u> </u>
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	ı
c:\pw_work\pwidot\steffenmk\d0375948\D7	74656-sht-plan.dgn	DRAWN -	REVISED -	ı
FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	

STATE OF ILLINOIS	
DEPARTMENT OF TRANSPORTATION	

BILL OF MATERIALS			F.A. RTE.	SECTION		
	CLARK CO LOCATIONS 19 - 21				D7 SAFETY 20	
		CLANK CO	LUCATIONS 19 -	21		
	CHEET	0.5	CHEETC CTA	TO CTA		

CONTRACT NO. 74656