# **CLARK COUNTY LOCATION 28**

## DARWIN FERRY RD - 2100 ST

**SIGNS** 

## BILL OF MATERIALS

SIGN TYPES BY LOCATION	UNITS		DIRECTION
ONE-DIRECTION LARGE ARROW (W1-6L) - 48" X 24"	EACH	1	ЕB
ONE-DIRECTION LARGE ARROW (W1-6R) - 48" X 24"	EACH	1	WB

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	16
TELESCOPING STEEL SIGN SUPPORT	FOOT	30

## **CLARK COUNTY LOCATION 29**

1830 ST - 550 RD

**SIGNS** 

BILL OF MA	CTERIALS	1

SIGN TYPES BY LOCATION	UNITS		DIRECTION
REVERSE CURVE (W1-4R) - 30" X 30"	EACH	2	NB SB

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	1 3
TELESCOPING STEEL SIGN SUPPORT	FOOT	33

## **CLARK COUNTY LOCATION 30**

<u>1830 ST - 1840 ST</u>

**SIGNS** 

#### **BILL OF MATERIALS**

SIGN TYPES BY LOCATION	UNITS		DIRECTION
REVERSE TURN (W1-3L) - 30" X 30"	EACH	2	NB SB

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	13
TELESCOPING STEEL SIGN SUPPORT	FOOT	33

TO STA.

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	
c:\pw_work\pwidot\steffenmk\d0375948\D7	74656-sht-plan.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTA
Default	PLOT DATE = 3/19/2014	DATE -	REVISED -	

		CLAR			TERIALS NS 28 - 30
RTATION		ULAII	K CO LC	JUATIO	13 20 - 30
	SCALE:	SHEET	OF	SHEETS	STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	D7 SAFETY 2014-2	VARIOUS	61	37	
		CONTRACT	NO. 7	4656	
ILLINOIS FED. AID PROJECT					