EFFINGHAM COUNTY LOCATION 1

1800 AVE - 1800 ST

SIGNS

SIGN TYPES BY LOCATION	UNITS		DIRECTION
TURN (W1-1L) - 30" X 30"	EACH	1	NB
TURN (W1-1R) - 30" X 30"	EACH	1	SB
ADVISORY SPEED (PLAQUE) (W13-1P) 20 MPH - 18" x 18"	EACH	2	NB SB

BILL OF MATERIALS

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	17
TELESCOPING STEEL SIGN SUPPORT	FOOT	36

EFFINGHAM COUNTY LOCATION 2

1450 ST - 1800 AVE

SIGNS

SIGN TYPES BY LOCATION	UNITS		DIRECTION
TWO-DIRECTION LARGE ARROW (W1-7) - 48" X 24"	EACH	1	SB

BILL OF MATERIALS

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	8
TELESCOPING STEEL SIGN SUPPORT	FOOT	15

EFFINGHAM COUNTY LOCATION 3

1325 ST - 225 AVE

SIGNS

SIGN TYPES BY LOCATION	UNITS		DIRECTION
TURN (W1-1L) - 30" X 30"	EACH	1	EB
TURN (W1-1R) - 30" X 30"	EACH	1	SB
ADVISORY SPEED (PLAQUE) (W13-1P) 20 MPH - 18" × 18"	EACH	2	SB EB

BILL OF MATERIALS

PAY ITEM DESCRIPTION	UNITS	
SIGN PANEL - TYPE 1	SQ FT	17
TELESCOPING STEEL SIGN SUPPORT	FOOT	36

Default	PLOT DATE = 3/19/2014	DATE -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
c:\pw_work\pwidot\steffenmk\d0375948\D7	74656-sht-plan.dgn	DRAWN -	REVISED -
FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS		F.A. RTE.	SECTION				
	FFFI	иснум	CO LOCA	TIONS 1	_ 3		D7 SAFETY 20
	LIII	IVUIIAIVI	CO LUCA	HONS I	- 3		
	CHEET	0.5	CHEETC	CT.	TO CT		

CONTRACT NO. 74656