

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				0014		0040		0043			
				BRIDGE REHAB	SIGN STRUCTURES	UTILITIES					
				80/20	FED/ST	80/20	FED/ST	80/20	FED/ST		
59000200	EPOXY CRACK INJECTION	FOOT	176		176						
66400505	CHAIN LINK FENCE, 8 FT	FOOT	1,884		1,884						
66409200	CHAIN LINK GATES, 8' X 8' DOUBLE	EACH	4		4						
67100100	MOBILIZATION	L SUM	1		1						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12		12						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1.5		1.5						
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20		20						
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	4,065		4,065						
X0320622	FIELD MEASUREMENTS	L SUM	1		1						
* X0321519	CONDUIT SUPPORT SYSTEM	L. SUM	1					1			
* X0325541	REMOVE EXISTING LIGHTING SYSTEM	L. SUM	1		1						
X0325583	REMOVE AND REINSTALL FINGER PLATE JOINT	EACH	3		3						
X0325941	ACCESS LADDER	EACH	3		3						
X0326275	RAILROAD RIGHT-OF-WAY ENTRY PERMIT	EACH	1		1						
X0326534	REMOVE AND REINSTALL EXISTING ALUMINUM PARAPET	FOOT	1,905		1,905						
X5870015	BRIDGE DECK CONCRETE SEALER	SO. FT.	193,439		193,439						
X6300231	STEEL POST, ATTACHED TO STRUCTURES	EACH	812		812						

* SPECIALTY ITEM



USER NAME - #USER#	DESIGNED - JAH	REVISED -
PLOT SCALE - #SCALE#	DRAWN - JAH	REVISED -
PLOT DATE - #DATE#	CHECKED - GRE	REVISED -
	DATE - 2/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
MLK BRIDGE OVER MISSISSIPPI RIVER

SCALE: N.T.S. SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
799	LBR. DRS-2	ST. CLAIR	156	4
CONTRACT NO. 76B03			ILLINOIS FED. AID PROJECT	