

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				80% FED / 20% STATE			
				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL 0005	URBAN 0005	SN 061-0082 0014	SN 061-0066 0040
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	25	25			
63200310	GUARDRAIL REMOVAL	FOOT	5725	5725			
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	58924	58924			
64300430	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	2		2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	14	7	7		
67100100	MOBILIZATION	L SUM	1	0.7	0.3		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1		1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.7	0.3		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.7	0.3		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5		0.5	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			

SUMMARY OF QUANTITIES				80% FED / 20% STATE			
				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL 0005	URBAN 0005	SN 061-0082 0014	SN 061-0066 0040
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.7	0.3		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.7	0.3		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.7	0.3		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1	
70106700	TEMPORARY RUMBLE STRIPS	EACH	12	6		6	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15934	11941	3993		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1077	406	671		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	113484	109784	3700		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	257		257		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1596	1290	306		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	98	48	50		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	43481	25088	18393		

* SPECIALTY ITEM

FILE NAME =	USER NAME = milleraj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ar\p\work\p\milleraj\0202388\05	6f28-ahp\plan.dgn	DRAWN -	REVISED -			327	(16,17,18)RS-3	MARION	83	5	
PLOT SCALE = 100,0000' / 1"	CHECKED -	REVISED -				CONTRACT NO. 76F28					
PLOT DATE = 3/20/2014	DATE -	REVISED -				SCALE: NTS	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT