

80/20 FED/STATE
CONSTRUCTION CODE
 FAP 582 FAU 9079

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				FAP 582	FAU 9079
				ROADWAY 0004 URBAN	ROADWAY 0004 URBAN
20200100	EARTH EXCAVATION	CU YD	3829	3336	493
21400100	GRADING AND SHAPING DITCHES	FOOT	40	40	
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	9397	7817	1580
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	1580	1580	
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SO YD	44.4		44.4
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SO YD	7509	5929	1580
44000100	PAVEMENT REMOVAL	SO YD	7509	5929	1580
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2004	2004	
44003100	MEDIAN REMOVAL	SO FT	6234	6234	
44004250	PAVED SHOULDER REMOVAL	SO YD	1310	1310	
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SO YD	1310	1310	
60263900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 11 FRAME AND GRATE EACH		5	5	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1942	1942	
60618320	CONCRETE MEDIAN SURFACE, 6 INCH	SO FT	15059	15059	

80/20 FED/STATE
CONSTRUCTION CODE
 FAP 582 FAU 9079

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				FAP 582	FAU 9079
				ROADWAY 0004 URBAN	ROADWAY 0004 URBAN
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	0.6	0.4
67201100	SEALING ABANDONED MONITORING WELLS	EACH	5	5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.6	0.4
70300100	SHORT TERM PAVEMENT MARKING	FOOT	546	503	43
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	94	94	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6204	5048.3	1155.7
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	85	85	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	152	112	40
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2690	2210	480
* 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOL	SO FT	94	94	
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	6204	5048.3	1155.7
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	85	85	
* 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	152	112	40

* SPECIALTY ITEM

FILE NAME *	USER NAME * USER#	DESIGNED - _____	REVISED - _____
FILE#		DRAWN - _____	REVISED - _____
MODEL NAME#	PLOT SCALE * SCALE#	CHECKED - _____	REVISED - _____
	PLOT DATE * DATE#	DATE - _____	REVISED - _____

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	60-5N-1	MADISON	73	3
CONTRACT NO. 76F41			ILLINOIS FED. AID PROJECT	

*FAP 582/FAU 9079