

PAVEMENT MARKING REMOVAL					
LOCATION				LENGTH	PAVEMENT MARKING REMOVAL
STA	TO	STA	DESCRIPTION	FOOT	SO FT
IL III NORTHBOUND					
202+88	TO	204+86	RT EDGE LINE	198.3	66.1
202+88	TO	204+86	SKIP DASH	198.3	16.5
204+86	TO	205+00	LTL LINE	14.2	4.7
204+86	TO	205+00	RT EDGE LINE	14.2	4.7
204+86	TO	205+00	SKIP DASH	14.2	3.3
205+00	TO	207+36	LTL LINE	235.8	78.6
205+00	TO	207+36	RT EDGE LINE	235.8	78.6
205+00	TO	207+36	STOP BAR		114.6
TOTAL					367.2

PAVEMENT REMOVAL					
LOCATION				LENGTH	PAVEMENT REMOVAL
STA	TO	STA	FOOT	FOOT	SOYD
NB LEFT TURN LANES					
202+87.5	TO	204+85	197.5		131.7
204+85	TO	205+00	15.0		20.0
205+00.	TO	206+86	186.0		248.0
206+86	TO	207+25.8	39.8		59.5
207+25.8	TO	208+16.3	90.5		144.8
208+16.3	TO	208+29.7	13.4		10.7
NB THRU LANES					
207+48.3	TO	210+00	251.7		671.2
210+00	TO	213+63	363.0		968.0
SB THRU LANES					
202+87.6	TO	205+00	212.4		590.0
205+00	TO	208+53.3	353.3		981.4
208+53.3	TO	208+72.3	19.0		30.0
208+72.3	TO	210+00	127.7		326.3
210+00	TO	213+63	363.0		927.7
SB LEFT TURN LANE					
206+70	TO	207+25.8	55.8		40.9
207+25.8	TO	208+29.7	103.9		180.1
208+29.7	TO	208+53.3	23.6		34.9
208+53.3	TO	210+00	146.7		195.6
210+00	TO	210+94	94.0		125.3
210+00	TO	213+63	363.0		242.0
CHAIN OF ROCKS ROAD					
24+83.7		28+00	316.3		843.5
28+00		28+90	90.0		267.0
28+90		29+60	70.0		469.9
TOTAL:					7508.5

SEALING ABANDONED MONITORING WELLS	
LOCATION	SEALING ABANDONED MONITORING WELLS
STA	EACH
IL III	
209+42.8	1
210+23.8	1
210+88.2	1
211+42.3	1
212+18.3	1
TOTAL:	5