

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ACF FAP 592 0005 M230L 07COL 07POL			ACF FAP 789 0005 M230L 07COL 07POL			ACM FAU 8890 0005 M230U 07COL 07POL		
				20% STATE 80% FED	50% CITY 50% STATE	100% CITY	20% STATE 80% FED	50% CITY 50% STATE	100% CITY	20% STATE 80% FED	50% CITY 50% STATE	100% CITY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16.1	4.3			8.9	1.0		1.9		
40600300	AGGREGATE (PRIME COAT)	TON	72	20.3			43.3	4.6		3.8		
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	2648	752.3			1590.2	170.4		135.1		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5296	1504.3			3180.5	340.8		270.4		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	6160	752.7			5407.3					
42400800	DETECTABLE WARNINGS	SQ FT	473	40			433					
44000300	CURB REMOVAL	FOOT	390	36			354					
44000400	GUTTER REMOVAL	FOOT	1032				1032					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	727	36		126.5	298			266.5		
44000600	SIDEWALK REMOVAL	SQ FT	6175	753			5422					
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	4	4								
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	377	157.3			136.1			71.6	12	
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	58.2	58.2								
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	278				278					

FILE NAME	USER NAME #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			FAP/U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -		SCALE:	SHEET 3	OF 4	SHEETS	STA.	TO STA.	MADISON	74	4
		CHECKED -	REVISED -								CONTRACT NO. 76G71		
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		