

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ACF FAP 592 0005			ACF FAP 789 0005			ACM FAU 8890 0005		
				20% STATE 80% FED	50% CITY 50% STATE	100% CITY	20% STATE 80% FED	50% CITY 50% STATE	100% CITY	20% STATE 80% FED	50% CITY 50% STATE	100% CITY
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	12325				7217	5048				
60260100	INLETS TO BE ADJUSTED	EACH	3			1			2			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3.4						3.4			
60600605	CONCRETE CURB, TYPE B	FOOT	379.5	35.5			344					
60602800	CONCRETE GUTTER, TYPE B	FOOT	1032				1032					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	334	36.5			297.5					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	393			126.5			266.5			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11	3			7			1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.3			0.6			0.1		
67100100	MOBILIZATION	L SUM	1	0.3			0.6			0.1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.3			0.6			0.1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.3			0.6		0.1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.3			0.6			0.1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	9			18			3		
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.3			0.6			0.1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5287	2391.5			2727			168.5		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1108	528.4			423			156.6		

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		FAP/U	SECTION	COUNTY	TOTAL	SHEET
#FILE#		DRAWN -	REVISED -				RTE.	(72, 56) RS-1, 65-2RS43	MADISON	74	5
	PLOT SCALE = *SCALE*	CHECKED -	REVISED -		SCALE:	SHEET 2 OF 4 SHEETS	STA.	TO STA.	CONTRACT NO. 76G71		
	PLOT DATE = *DATE*	DATE -	REVISED -		ILLINOIS FED. AID PROJECT						