


EXIST. CURVE C13
 PI STA. = 53+59.72
 Δ = 61° 55' 19" (LT)
 D = 59° 45' 06"
 R = 95.89'
 T = 57.53'
 L = 103.63'
 E = 15.93'
 θ = -----
 T.R. = -----
 S.E. RUN = -----
 P.C. STA. = 53+02.19
 P.T. STA. = 54+05.82



STATION	PAVEMENT MARKING SCHEDULE														SHORT TERM PAVEMENT MARKING (FOOT)	RAISED RELECTIVE PAVEMENT MARKERS (EACH)		RAISED RELECTIVE PAVT. MRK. REMOVAL (EACH)	WORK ZONE PAVEMENT MRK. REM. (SQ FT)	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS (SQ FT)	
	THERMOPLASTIC PAVEMENT MARKING LINE - 4" (FOOT)			TEMPORARY PAVEMENT MARKING LINE - 4" (FOOT)			THERMOPLASTIC PAVEMENT MARKING LINE - 6" (FOOT)	TEMPORARY PAVEMENT MARKING LINE - 6" (FOOT)	THERMOPLASTIC PAVEMENT MARKING LINE - 8" (FOOT)	TEMPORARY PAVEMENT MARKING LINE - 8" (FOOT)	THERMOPLASTIC PAVEMENT MARKING LINE - 12" (FOOT)	TEMPORARY PAVEMENT MARKING LINE - 12" (FOOT)	THERMOPLASTIC PAVEMENT MARKING LINE - 24" (FOOT)	TEMPORARY PAVEMENT MARKING LINE - 24" (FOOT)		1-WAY CRYSTAL	2-WAY AMBER					
	SOLID WHITE	SKIP-DASH YELLOW	SOLID YELLOW	SOLID WHITE	SKIP-DASH YELLOW	SOLID YELLOW										16	16					
51+00.00 TO 53+20.50	422.4	0.0	626.3	422.4	0.0	626.3	199.4	199.4	0.0	0.0	21.4	21.4	0.0	0.0	101.4	101.4	0	16	16	525.9	0.0	0.0
TOTAL THIS PAGE	1048.7			1048.7			199.4	199.4	0.0	0.0	21.4	21.4	0.0	0.0	101.4	101.4	16		16	525.9	0.0	0.0
SUB-TOTAL	29325.9			29325.9			848.7	848.7	213.1	213.1	465.8	465.8	1250.0	1250.0	4542.9	417		417	15944.5	941.8	941.8	

FILE NAME =	USER NAME = \$USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING PLAN			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL		DRAWN -	REVISED -					* (7Z, 56)RS-1, 65-2RS-4	MADISON	74	70	
	PLOT SCALE = \$SCALE*	CHECKED -	REVISED -					CONTRACT NO. 76G71				
	PLOT DATE = \$DATE*	DATE -	REVISED -					FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			