

SUMMARY OF QUANTITIES

100% STATE
CONSTRUCTION CODE
ROADWAY 0005

URBAN

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CAMP JACKSON ROAD / IL ROUTE 157 (LAURALEE TO IL ROUTE 13/157) | NORTH 89TH STREET (NORTH OF STATE STREET) | NORTH 89TH STREET (NORTH OF ST. CLAIR AVENUE) | 13TH STREET |
|----------|---|-------|----------------|---|---|---|-------------|
| 35101600 | AGGREGATE BASE COURSE, TYPE B 4" | SQ YD | 23 | | 23 | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 14 | 7 | 4 | 2 | 1 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 56 | 30 | 18 | 5 | 3 |
| 40600637 | LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70 | TON | 1,342 | 645 | 480 | 140 | 77 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 2,075 | 770 | 280 | 227 | 798 |
| 40600990 | TEMPORARY RAMP | SQ YD | 1,605 | 494 | 151 | 162 | 798 |
| 40603315 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 | TON | 1,396 | | 960 | 281 | 155 |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 1,288 | 1,288 | | | |
| 40800050 | INCIDENTAL HOT-MIX ASPHALT SURFACING | TON | 37 | 31 | 4 | 2 | |
| 42400300 | PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH | SQ FT | 250 | | | | 250 |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 25 | | | | 25 |
| 44000153 | HOT-MIX ASPHALT SURFACE REMOVAL, 1" | SQ YD | 18,886 | 18,886 | | | |
| 44000156 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4" | SQ YD | 14,432 | | 11,255 | 3,177 | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 1,842 | | | | 1,842 |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 4 SHEETS STA. TO STA.

| | | | | |
|---|---------|-----------|--------------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| VAR. | * | ST. CLAIR | 19 | 3 |
| * DIST 8 RESURFACING 2014-5 | | | CONTRACT NO. 76H23 | |
| FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT | | | | |

FILE NAME: 76H23-SH-URBAN SUMMARY-B1.dgn
USER NAME: mmokin
MODEL NAME: Default
PLOT SCALE: 28.8000' / in.
PLOT DATE: 4/15/2014

DESIGNED - TTB
DRAWN - TTB
CHECKED - JAH
DATE - 4/10/14

REVISED -
REVISED -
REVISED -
REVISED -

14