

SIDEROAD SCHEDULE								
STATION	SIDE	ROAD NAME	EXISTING SURFACE	LENGTH (FOOT)	WIDTH (FOOT)	BITUMINOUS MATERIALS (PRIME COAT) TON	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ YD	INCIDENTAL HMA SURFACING TON
CAMP JACKSON ROAD / IL ROUTE 157 (LAURALEE TO IL ROUTE 13/157)								
266+21	LT	RENOIS LANE	BITUMINOUS	91	7.5	0.024	75.8	2.7
281+06	RT	MILLSTADT ROAD	BITUMINOUS	76	7.5	0.020	63.3	2.2
289+80	LT	CHURCH ROAD	BITUMINOUS	48	7.5	0.013	40.0	1.4
299+37	LT	TUSKEGEE DRIVE	BITUMINOUS	57	7.5	0.015	47.5	1.7
304+01	LT	BOCLAIR DRIVE	BITUMINOUS	13	7.5	0.003	10.8	0.4
305+77	LT	DUNLAP DRIVE	BITUMINOUS	24	7.5	0.006	20.0	0.7
307+17	LT	BEATRICE STREET	BITUMINOUS	22	7.5	0.006	18.3	0.6
"LAURALEE TO IL ROUTE 13/157" TOTAL						0.09	276	10
NORTH 89TH STREET (NORTH OF STATE STREET)								
5+06	LT	WASHINGTON STREET	BITUMINOUS	40	3.5	0.005	15.6	0.2
15+62	RT	HILLSLOPE DRIVE	CONCRETE	68	3.5	0.008	26.4	0.4
27+73	LT	VIEUX CARRE DRIVE	CONCRETE	130	3.5	0.016	50.6	0.7
30+85	RT	WOESTBOUL STREET	BITUMINOUS	92	3.5	0.011	35.8	0.5
"NORTH OF STATE STREET" TOTAL						0.04	129	2
NORTH 89TH STREET (NORTH OF ST. CLAIR AVENUE)								
10+09	LT	CALIFORNIA DRIVE	CONCRETE	166	3.5	0.020	64.6	0.9
"NORTH OF ST. CLAIR AVENUE" TOTAL						0.02	65	1
TOTAL						0.1	470	13

SIGNING SCHEDULE					
LOCATION	OFFSET	TYPE	SIZE	SIGN PANEL TYPE 1 SQ FT	TELESCOPING STEEL SIGN SUPPORT FT
CAMP JACKSON ROAD / IL ROUTE 157 (LAURALEE TO IL ROUTE 13/157)					
283+05	28' LT.	W10-1	36" DIA.	7.07	15
289+38	36.5' RT.	W10-1	36" DIA.	7.07	15
"LAURALEE TO IL ROUTE 13/157" TOTAL				15	30
NORTH 89TH STREET (NORTH OF ST. CLAIR AVENUE)					
1+53	18' LT.	W1-8R	18" X 24"	3.00	14
1+86	18' LT.	W1-8L	18" X 24"	3.00	16
1+86	18' LT.	W1-8R	18" X 24"	3.00	16
2+19	18' LT.	W1-8L	18" X 24"	3.00	16
2+19	18' LT.	W1-8R	18" X 24"	3.00	16
2+52	18' LT.	W1-8L	18" X 24"	3.00	16
2+52	18' LT.	W1-8R	18" X 24"	3.00	16
2+88	18' LT.	W1-8L	18" X 24"	3.00	14
"NORTH OF ST. CLAIR AVENUE" SUBTOTAL				24	76
TOTALS				39	106

GUARDRAIL SCHEDULE					
STATION TO	STATION	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6-FOOT POSTS FOOT	GUARDRAIL MARKERS, TYPE A EACH	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT EACH	TERMINAL MARKER - DIRECT APPLIED EACH
NORTH 89TH STREET (NORTH OF ST. CLAIR AVENUE)					
1+37	1+59		2	1	1
1+59	2+65	75	4		
2+65	2+87		2	1	1
"NORTH OF ST. CLAIR AVENUE" TOTAL		75	8	2	2
TOTAL		75	8	2	2

PAVEMENT MARKING SCHEDULE												
LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING					RAISED REFLECTIVE PAVEMENT MARKERS				PRISMATIC CURB REFLECTOR ONE WAY AMBER EA	
		LETTERS & SYMBOLS SQ FT	4" LINE		12" LINE		24" LINE	TWO WAY AMBER EA	ONE WAY AMBER EA	WHITE OPAQUE EA		PAINT CURB YELLOW (FT)
CAMP JACKSON ROAD / IL ROUTE 157 (LAURALEE TO IL ROUTE 13/157)												
258+76 TO 307+41 (SEE PLAN SHEETS)	STOP BAR					75						
	SKIP DASH		131	455					23			
	SINGLE SOLID		10,234	1,905						14	1,184	63
	DOUBLE SOLID			6,315					38	42		
	DIAGONAL				270	101						
	LETTERS & SYMBOLS	190										
"LAURALEE TO IL ROUTE 13/157" TOTAL		190	10,365	8,675	270	101	75	61	42	14	1,184	63
NORTH 89TH STREET (NORTH OF STATE STREET)												
0+50 TO 40+25	STOP BAR					48						
	SKIP DASH			994					50			
	SINGLE SOLID		7,531									
"NORTH OF STATE STREET" TOTAL			7,531	994			48	50				
NORTH 89TH STREET (NORTH OF ST. CLAIR AVENUE)												
1+35 TO 14+74	SKIP DASH			335					17			
"NORTH OF ST. CLAIR AVENUE" TOTAL				335				17				
13TH STREET												
0+36 TO 3+79	STOP BAR					24						
	SKIP DASH			55					3			
	SINGLE SOLID		555	28								
13TH STREET TOTAL			555	83		24		3				
TOTALS		190	18,451	10,087	270	101	147	131	42	14	1,184	63

PATCHING SCHEDULE					
LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	PAVEMENT PATCHING, TYPE II, 10 INCH SQ YD	PAVEMENT PATCHING, TYPE III, 10 INCH SQ YD	PAVEMENT PATCHING, TYPE IV, 10 INCH SQ YD
CAMP JACKSON ROAD / IL ROUTE 157 (LAURALEE TO IL ROUTE 13/157)					
258+86, LT.	20	12			26.7
258+86, RT.	20	12			26.7
263+40, LT.	20	12			26.7
263+40, RT.	20	12			26.7
269+83	6	12	8.0		
270+35, LT.	20	12		26.7	
270+35, RT.	20	12		26.7	
275+06	200	6			133.3
278+10	20	15			33.3
278+51	6	15	10.0		
279+13	10	15		16.7	
280+19	50	15			83.3
284+46, LT.	6	21	14.0		
284+46, RT.	6	21	14.0		
285+39, LT.	6	23		15.3	
285+39, RT.	6	14	9.3		
287+15, LT.	6	15	10.0		
287+15, RT.	6	14	9.3		
290+89	10	12	13.3		
290+91	6	12	8.0		
293+76, LT.	40	12			53.3
293+76, RT.	40	12			53.3
"LAURALEE TO IL ROUTE 13/157" SUBTOTAL			96.0	85.3	463.3
ANTICIPATED FAILURES (15%)			14.4	12.8	69.5
"LAURALEE TO IL ROUTE 13/157" TOTAL			111	99	533
NORTH 89TH STREET (NORTH OF STATE STREET)					
0+58	15	20			33.3
1+86	15	18			30.0
3+82, LT.	6	15	10.0		
3+82, RT.	6	15	10.0		
7+77	6	12	8.0		
7+81	15	12		20.0	
9+09, LT.	6	12	8.0		
9+09, RT.	6	12	8.0		
9+67, LT.	6	12	8.0		
9+67, RT.	6	12	8.0		
10+29, LT.	6	12	8.0		
10+29, RT.	6	12	8.0		
11+63, LT.	6	12	8.0		
11+63, RT.	6	12	8.0		
12+03, LT.	6	12	8.0		
12+03, RT.	6	12	8.0		
13+56, LT.	6	12	8.0		
13+56, RT.	6	12	8.0		
16+86, LT.	6	12	8.0		
16+86, RT.	6	12	8.0		
18+17, LT.	6	12	8.0		
18+17, RT.	6	12	8.0		
19+40	6	12	8.0		
22+21	80	11			97.8
35+20, LT.	6	12	8.0		
35+20, RT.	6	12	8.0		
36+46, LT.	6	12	8.0		
36+46, RT.	6	12	8.0		
39+63, LT.	6	12	8.0		
39+63, RT.	6	12	8.0		
"NORTH OF STATE STREET" SUBTOTAL			212.0	20.0	161.1
ANTICIPATED FAILURES (15%)			31.8	3.0	24.2
"NORTH OF STATE STREET" TOTAL			244	23	186
NORTH 89TH STREET (NORTH OF ST. CLAIR AVENUE)					
9+14	6	10	6.7		
11+15, LT.	6	10	6.7		
11+15, RT.	6	10	6.7		
13+01	6	10	6.7		
"NORTH OF ST. CLAIR AVENUE" SUBTOTAL			26.7		
ANTICIPATED FAILURES (15%)			4.0		
"NORTH OF ST. CLAIR AVENUE" TOTAL			31		
13TH STREET					
1+07	40	9			40.0
1+96, LT.	6	18		12.0	
1+96, RT.	6	18		12.0	
13TH STREET SUBTOTAL				24.0	40.0
ANTICIPATED FAILURES (15%)				3.6	6.0
13TH STREET TOTAL				28	46
TOTAL			386	150	765

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FILE NAME = 76h23-shr-QUAN SCHED-02.dgn
USER NAME = mmcklin
MODEL NAME = Default
PLOT SCALE = 20.0000' / in.
PLOT DATE = 4/11/2014

DESIGNED - TTB
DRAWN - TTB
CHECKED - JAH
DATE - 4/10/14

REVISED -
REVISED -
REVISED -
REVISED -

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. SECTION COUNTY TOTAL SHEET NO.
VAR. * ST. CLAIR 19 10
* DIST 8 RESURFACING 2014-5 CONTRACT NO. 76H23
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT