IL-15 CLASS A PAVEMENT PATCHING SCHEDULE EASTBOUND

PATCH #	MILE	SHOULDER TYPE	LANE	LENGTH (FT)	LANE WIDTH (FT)	CLASS A PATCH TYPE I 11 " (SQ YD)	CLASS A PATCH TYPE II 11 " (SQ YD)	CLASS A PATCH TYPE III 11 " (SQ YD)	CLASS A PATCH TYPE IV 11 " (SQ YD)	TIE BARS (EACH)	PATCHING REINFORCEMENT (SQ YD)	SAWCUT (FT)
1	0.000	HMA	1	12.00	6.00		8.00				8.00	48.00
2	0.000	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
3	0.030	HMA	1	30.00	6.00			20.00		14	20.00	84.00
4	0.050	HMA	1	12.00	6.00		8.00				8.00	48.00
5	0.050	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
6	0.100	HMA	1	12.00	6.00		8.00				8.00	48.00
7	0.100	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
8	0.140	HMA	1	12.00	6.00		8.00				8.00	48.00
9	0.140	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
10	0.200	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
11	0.220	HMA	1	12.00	6.00		8.00				8.00	48.00
12	0.220	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
13	0.240	HMA	1	8.00	6.00		5.33				5.33	40.00
14	0.240	CONCRETE	2	8.00	6.00		5.33				5.33	48.00
15	0.260	CONCRETE	2	50.00	6.00				33.33	24	33.33	174.00
16	0.300	HMA	1	12.00	6.00		8.00				8.00	48.00
17	0.300	HMA	3	12.00	6.00		8.00				8.00	48.00
18	0.340	HMA	1	12.00	6.00		8.00				8.00	48.00
19	0.340	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
20	0.340	HMA	3	12.00	6.00		8.00				8.00	48.00
21	0.400	CONCRETE	2	8.00	6.00		5.33				5.33	48.00
22	0.500	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
23	0.600	HMA	1	12.00	10.00		13.33				13.33	64.00
24	0.600	CONCRETE	2	12.00	8.00		10.67				10.67	68.00
25	0.600	HMA	3	6.00	6.00	4.00					4.00	36.00
26	0.620	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
27	0.630	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
28	0.640	CONCRETE	2	30.00	6.00			20.00		14	20.00	114.00
29	0.670	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
30	0.700	CONCRETE	2	12.00	8.00		10.67				10.67	68.00
31	0.700	HMA	3	12.00	6.00		8.00				8.00	48.00
32	0.800	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
33	1.000	HMA	1	12.00	6.00		8.00				8.00	42.00
34	1.000	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
35	1.050	CONCRETE	2	20.00	6.00		13.33			9	13.33	84.00
36	1.100	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
37	1.200	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
38	1.300	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
39	1.310	CONCRETE	2	20.00	6.00		13.33			9	13.33	84.00
40	1.320	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
41	1.330	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
42	1.350	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
43	1.370	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
44	1.400	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
45	1.450	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
46	1.450	HMA	3	12.00	6.00		8.00				8.00	48.00
47	1.500	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
48	1.500	HMA	3	10.00	6.00		6.67				6.67	44.00
49	1.510	CONCRETE	2	10.00	6.00		6.67				6.67	54.00
50	1.520	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
51	1.530	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
52	1.540	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
53	1.550	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
54	1.550	HMA	3	6.00	6.00	4.00					4.00	36.00
55	1.580	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
56	1.590	CONCRETE	2	12.00	8.00		10.67				10.67	68.00
57	1.600	CONCRETE	2	6.00	6.00	4.00					4.00	42.00
58	1.630	HMA	1	12.00	6.00		8.00				8.00	48.00
59	1.630	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
60	1.630	HMA	3	12.00	6.00		8.00				8.00	48.00
61	1.650	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
62	1.650	HMA	3	12.00	6.00		8.00				8.00	48.00
63	1.670	HMA	1	12.00	12.00			16.00			16.00	72.00
64	1.670	CONCRETE	2	12.00	6.00		8.00				8.00	60.00
65	1.670	HMA	3	8.00	12.00		10.67				10.67	64.00
		SUBTOTAL:				76.00	352.00	56.00	33.33	70	517.33	3578.00
		ANTICIPATED FAILURES (15%):				11.40	52.80	8.40	5.00	11	77.60	536.70
		TOTAL:				87.40	404.80	64.40	38.33	81	594.93	4114.70

NOTE: LANE 1 = LEFT LANE
LANE 2 = MIDDLE LANE
LANE 3 = RIGHT LANE

* FAP 103/674

FILE NAME = c:\pw_work\pwidot\lagemannge\d0388138\D76H25-sht-plan.dgn	USER NAME = lagemannge	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/15/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	29-I-1, (31,410,410-1)I-1	ST.CLAIR	17	12
		CONTRACT NO. 76H25		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT