

IL ROUTE 158 PAVEMENT MARKING SCHEDULE						
PATCH NUMBER	MILE MARKER	LENGTH FOOT	4" WHITE SKIP DASH PAINT PAV. MARKING	4" SOLID WHITE PAINT PAV. MARKING	4" SOLID YELLOW PAINT PAV. MARKING	RAISED REFLECTIVE PAVEMENT MARKER
			FOOT	FOOT	FOOT	EACH
1	0.3	90		90.00		2.00
2	0.4	240		240.00		3.00
3	0.6	6	1.50	6.00		1.00
4	0.7	4	1.00	4.00		1.00
5	0.8	30	7.50	30.00		1.00
6	0.8	160		160.00		2.00
7	1	560		560.00		7.00
8	1.1	50		50.00		1.00
9	1.1	12	3.00	12.00		1.00
10	1.1	6	1.50		6.00	1.00
11	1.2	15	3.75		15.00	1.00
12	1.2	15	3.75	15.00		1.00
13	1.2	4	1.00		4.00	1.00
14	1.2	6	1.50		6.00	1.00
15	1.2	25	6.25		25.00	1.00
16	1.2	25	6.25	25.00		1.00
17	1.2	25	6.25		25.00	1.00
18	1.2	10	2.50	10.00		1.00
19	1.2	10	2.50		10.00	1.00
20	1.2	6	1.50	6.00		1.00
21	1.3	20	5.00	20.00		1.00
22	1.3	10	2.50	10.00		1.00
23	1.3	6	1.50	6.00		1.00
24	1.3	20	5.00		20.00	1.00
25	1.3	10	2.50	10.00		1.00
26	1.3	30	7.50	30.00		1.00
27	1.6	6	1.50		6.00	1.00
28	1.6	15	3.75	15.00		1.00
29	1.7	25	6.25	25.00		1.00
30	1.8	10	2.50	10.00		1.00
31	1.8	12	3.00	12.00		1.00
32	1.8	6	1.50	6.00		1.00
33	1.9	12	3.00	12.00		1.00
34	1.9	12	3.00	12.00		1.00
35	2.2	6	1.50	6.00		1.00
36	2.2	12	3.00		12.00	1.00
37	2.2	12	3.00	12.00		1.00
38	2.8	6	1.50	6.00		1.00
39	2.9	150		150.00		2.00
40	2.9	20	5.00	20.00		1.00
41	3.1	10	2.50	10.00		1.00
42	3.8	20	5.00	20.00		1.00
NORTHBOUND						
43	0.3	10	2.50	10.00		1.00
44	0.4	25	6.25	25.00		1.00
45	1.2	6	1.50	6.00		1.00
46	1.2	12	3.00	12.00		1.00
47	1.4	6	1.50	6.00		1.00
48	1.4	35	8.75	35.00		1.00
49	2.1	25	6.25	25.00		1.00
50	2.1	25	6.25	25.00		1.00
51	2.1	6	1.50		6.00	1.00
52	2.3	20	5.00	20.00		1.00
53	2.3	6	1.50	6.00		1.00
54	2.4	12	3.00	12.00		1.00
55	2.4	12	3.00		12.00	1.00
56	2.4	40	10.00	40.00		1.00
57	2.4	25	6.25	25.00		1.00
58	2.5	10	2.50	10.00		1.00
59	2.5	90		90.00		1.00
60	2.5	40	10.00	40.00		1.00
61	2.6	15	3.75	15.00		1.00
62	2.6	110			110.00	2.00
63	2.6	12	3.00	12.00		1.00
64	2.6	35	8.75	35.00		1.00
65	2.6	210			210.00	3.00
66	2.6	12	3.00	12.00		1.00
67	2.6	25	6.25	25.00		1.00
68	2.6	15	3.75	15.00		1.00
69	2.6	10	2.50		10.00	1.00
70	2.6	20	5.00	20.00		1.00
71	3.1	6	1.50	6.00		1.00
72	3.1	6	1.50	6.00		1.00
73	3.1	4	1.00	4.00		1.00
74	3.1	4	1.00	4.00		1.00
75	3.3	200		200.00		3.00
76	3.4	6	1.50	6.00		1.00
77	3.4	90		90.00		1.00
78	3.4	35	8.75	35.00		1.00
79	3.4	35	8.75	35.00		1.00
80	3.7	12	3.00		12.00	1.00
81	3.7	12	3.00	12.00		1.00
82	3.7	70		70.00		1.00
83	3.8	35	8.75	35.00		1.00
84	3.8	35	8.75	35.00		1.00
85	3.8	6	1.50	6.00		1.00
86	4	12	3.00	12.00		1.00
RAMP 64 EB TO 158 NB						
87	0.1	150		150.00		2.00
88	0.1	35	8.75	35.00		1.00
89	0.2	40	10.00	40.00		1.00
			305.25	2902.00	489.00	106.00
			305.00	2902.00	489.00	106.00
			4,239			106

* FAP 103674

FILE NAME =	USER NAME = lagemannge	DESIGNED -	REVISED -
c:\pwork\pwork\lagemannge\103388138\0376H25-sht-plan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/15/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	29-I-1, (31,410,410-1)I-1	ST. CLAIR	17	16
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76H25	