

PATCHING SCHEDULE - 5 OF 5

LOCATION MILE MARKER	WIDTH FOOT	LENGTH FOOT	LANE #	CLASS A PATCHES, TYPE I, 10 INCH	CLASS A PATCHES, TYPE II, 10 INCH	CLASS A PATCHES, TYPE III, 10 INCH	CLASS A PATCHES, TYPE IV, 10 INCH	TIE BARS 3/4"	PATCHING REINFORCEMENT	SAW CUTS
				SQ YD	SQ YD	SQ YD	SQ YD	EACH	SQ YD	FOOT
SOUTHBOUND										
STARTING MILE MARKER		23.6								
19.8	6	6	3	4					4	30
19.8	6	6	2	4					4	30
19.8	6	66	3				44	32	44	90
19.8	6	12	3		8				8	36
19.7	6	6	3	4					4	30
19.7	6	12	3		8				8	36
19.7	6	6	2	4					4	30
19.6	6	12	1		8				8	36
19.6	6	12	2		8				8	36
19.6	6	12	1		8				8	36
19.6	6	12	2		8				8	36
19.6	6	12	3		8				8	36
19.5	6	12	3		8				8	36
19.5	6	6	2	4					4	30
19.5	6	12	1		8				8	36
19.5	6	12	2		8				8	36
19.5	6	12	3		8				8	36
19.5	8	12	2		11				11	44
19.4	6	12	3		8				8	36
19.3	6	8	3		5				5	32
19.3	6	45	2				30	22	30	69
19.3	6	6	3	4					4	30
19.3	6	6	3	4					4	30
19.2	12	12	2			16			16	60
19.2	12	12	3			16			16	60
19.2	8	12	1		11				11	44
19.2	6	12	1		8				8	36
19.2	6	12	2		8				8	36
19.2	6	12	3		8				8	36
19	6	12	3		8				8	36
19	6	12	3		8				8	36
19	6	12	1		8				8	36
19	6	12	2		8				8	36
19	6	6	2	4					4	30
18.9	12	6	1		8				8	54
18.9	12	6	2		8				8	54
18.9	12	6	3		8				8	54
18.9	12	6	3		8				8	54
18.9	12	20	3				27	9	27	68
18.8	6	12	1		8				8	36
18.8	6	12	2		8				8	36
18.8	8	12	3		11				11	44
18.8	6	12	1		8				8	36
18.8	6	12	2		8				8	36
18.6	6	6	3	4					4	30
18.5	6	6	1	4					4	30
18.5	12	20	2				27	9	27	68
18.5	10	12	3		13				13	52
18.4	8	12	3		11				11	44
18.4	6	12	2		8				8	36
18.4	8	6	3		5				5	38
18.4	6	12	3		8				8	36
18.3	10	12	3		13				13	52
18.3	8	12	3		11				11	44
18.3	6	12	3		8				8	36
18.3	6	12	3		8				8	36
18.3	6	12	3		8				8	36
18.2	6	12	3		8				8	36
18.2	6	12	3		8				8	36
16.6	6	12	1		8				8	36
16.6	6	12	2		8				8	36
16.6	6	12	3		8				8	36
16.3	12	12	3			16			16	60
16.2	6	6	3	4					4	30
15.1	12	10	3		13				13	58
6.5	8	12	1		11				11	44
6.4	8	12	1		11				11	44
6.4	6	6	2	4					4	30
6.4	6	6	2	4					4	30
6.4	6	6	2	4					4	30
6.4	6	6	2	4					4	30
6.4	6	12	1		8				8	36
6.1	6	60	2				40	29	40	84
6.1	8	12	1		11				11	44
6.1	6	60	2				40	29	40	84
6.1	6	6	2	4					4	30
6.1	6	10	2		7				7	34
6.1	6	6	3	4					4	30
6.1	6	12	2		8				8	36
SOUTHBOUND SUB-TOTAL				68	455	48	207	130	778	3247

PATCHING SCHEDULE - SUMMARY

	CLASS A PATCHES, TYPE I, 10 INCH	CLASS A PATCHES, TYPE II, 10 INCH	CLASS A PATCHES, TYPE III, 10 INCH	CLASS A PATCHES, TYPE IV, 10 INCH	TIE BARS 3/4"	PATCHING REINFORCEMENT	SAW CUTS
	SQ YD	SQ YD	SQ YD	SQ YD	EACH	SQ YD	FOOT
NORTHBOUND TOTAL	24	709	52	293	106	1079	4275
SOUTHBOUND TOTAL	348	800	157	247	225	1553	7379
TOTAL	372	1509	209	541	331	2631	11654
15% ALLOWANCE FOR FAILURES	56	227	32	82	50	395	1749
GRAND TOTAL	428	1736	241	623	381	3026	13403