

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	Existing Length (Inform. Only)	GUARDRAIL REMOVAL	SPBGR TYPE A, 6 FT. POSTS	TRAFFIC BARRIER TERMINAL, TY. 1 SPL. (TANG)	SPBGR ATTACHED TO STRUCTURE	TERMINAL MARKERS - DA	GUARDRAIL MARKERS TY. A	STONE RIPRAP, CLASS A5
	FOOT	FOOT	FOOT	EACH	FOOT	EACH	EACH	TON
LOCATION 4 - IL 14 IN FRANKLIN CO.								
028-7049 (North Side)								
LT 20+50.00				1		1		
LT 20+65.00 TO LT 21+65.00	100	100						
LT 21+00.00 TO LT 21+37.50					37.5		4	
LT 21+92.00				1		1		
028-7049 (South Side)								
RT 20+78.00				1		1		30
RT 21+00.00 TO RT 22+00.00	100	100						
RT 21+28.00 TO RT 21+65.50					37.5		4	
RT 22+16.00				1		1		
028-7051 (North Side)								
LT 34+05.00				1		1		
LT 34+30.00 TO LT 35+20.00	90	90						
LT 34+55.00 TO LT 34+92.50					37.5		4	
LT 35+43.00				1		1		
028-7051 (South Side)								
RT 33+82.00				1		1		
RT 34+00.00 TO RT 34+90.00	90	90						
RT 34+32.00 TO RT 34+69.50					37.5		4	
RT 35+20.00				1		1		
Exist. Guardrail over 18" pipe (North Side)								
LT 103+64.00				1		1		
LT 103+64.00 TO LT 106+34.00	270	270						
LT 104+14.00 TO LT 105+76.50			162.5				4	
LT 106+26.50				1		1		
Exist. Guardrail over 18" pipe (North Side)								
RT 103+64.00				1		1		
RT 103+64.00 TO RT 105+64.00	200	200						
RT 104+14.00 TO RT 105+14.00			100.0				4	
RT 105+64.00				1		1		
PROJECT TOTALS:		850	262.5	12	150.0	12	24	30

NOTE 1: ANY WIDENING AND EXTRA DIRT NECESSARY TO CONSTRUCT THE TYPE 1, SPECIAL (TANGENT) GUARDRAIL TERMINAL SHALL BE INCLUDED IN THE COST OF THE **TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)**.

NOTE 2: STONE RIPRAP, CLASS A5 SHALL BE PLACED AT LOCATION INDICATED AND AS DIRECTED BY THE ENGINEER.

- VARIOUS ROUTES
- VARIOUS COUNTIES

FILE NAME =	USER NAME = mccordkr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GUARDRAIL SCHEDULE	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	ei:\pw\work\p1\dot\mccordkr\d0371602\78396-sh1-plan.dgn	DRAWN -	REVISED -			•	D9 SAFETY 2014-2	••	17	8
	PLOT SCALE = 100.0000' / 1".	CHECKED -	REVISED -		SCALE:					
	PLOT DATE = 3/20/2014	DATE -	REVISED -		SHEET	OF	SHEETS	STA.	TO	STA.
										ILLINOIS FED. AID PROJECT
										CONTRACT NO. 78396