

SEEDING AND EROSION CONTROL SCHEDULE

| LOCATION STATION TO STATION | SEEDING, CLASS 1B | SEEDING, CLASS 7 | NITROGEN FERTILIZER NUTRIENT | PHOSPHORUS FERTILIZER NUTRIENT | POTASSIUM FERTILIZER NUTRIENT | AGRICULTURAL GROUND LIMESTONE | MULCH, METHOD 2 | EROSION CONTROL BLANKET | TEMP. DITCH CHECKS | INLET AND PIPE PROTECTION | PERIMETER EROSION BARRIER | REMARKS |
|--------------------------------|----------------------|---------------------|------------------------------------|--------------------------------------|-------------------------------------|-------------------------------------|--------------------|-------------------------------|--------------------------|---------------------------------|---------------------------------|---------|
| | ACRE | ACRE | POUND | POUND | POUND | TON | ACRE | SQ YD | FOOT | EACH | FOOT | |
| RUSHING DRIVE | | | | | | | | | | | | |
| 162+67.29 RT TO 165+52. RT | 0.05 | 0.05 | 8.0 | 6.0 | 6.0 | 0.1 | 0.1 | | | | 285 | |
| 162+67.29 LT TO 163+19. LT | 0.01 | 0.01 | 1.6 | 1.2 | 1.2 | 0.0 | 0.0 | | | | 50 | |
| 165+50. LT TO 166+60. LT | 0.06 | 0.06 | 9.6 | 7.2 | 7.2 | 0.1 | 0.1 | | | | 120 | |
| IL 148 | | | | | | | | | | | | |
| 59+95.81 LT TO 65+05 LT | 0.50 | 0.50 | 80.0 | 60.0 | 60.0 | 1.0 | 1.0 | | | | | |
| 60+50 LT | | | | | | | | | 11 | | | |
| 60+50. LT TO 63+25. LT | | | | | | | | 122 | | | | |
| 61+30 LT | | | | | | | | | 11 | | | |
| 62+08 LT | | | | | | | | | 11 | | | |
| 62+85 LT | | | | | | | | | | 1 | | |
| 63+30 LT | | | | | | | | | | 1 | | |
| 63+70 LT | | | | | | | | | | 1 | | |
| 63+75. LT TO 64+72. LT | | | | | | | | 43 | | | | |
| 64+83 LT | | | | | | | | | | 1 | | |
| 65+69 LT | | | | | | | | | | 1 | | |
| TOTALS | 0.6 | 0.6 | 99 | 74 | 74 | 1.2 | 1.2 | 165 | 33 | 5 | 455 | |