SUMMARY OF QUANTITIES

CONSTRUCTION CODE	
COUNTY	WILLIAMSON
FUNDING	80% FEDERAL 20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0005 URBAN
20200100	EARTH EXCAVATION	CU YD	75	75
20400100	BORROW EXCAVATION	CU YD	241	241
20800150	TRENCH BACKFILL	CU YD	17	17
25000115	SEEDING, CLASS 1B	ACRE	0.6	0.6
25000350	SEEDING, CLASS 7	ACRE	0.6	0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	99	99
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	74	74
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	74	74
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.2	1.2
25100115	MULCH, METHOD 2	ACRE	1.2	1.2
25100630	EROSION CONTROL BLANKET	SQ YD	165	165
28000305	TEMPORARY DITCH CHECKS	FOOT	33	33
28000400	PERIMETER EROSION BARRIER	FOOT	455	455
28000500	INLET AND PIPE PROTECTION	EACH	6	6

14