SUMMARY OF QUANTITIES			COUNTY	CONSTRUCTION CODE
			FUNDING	WILLIAMSON
				80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0005 URBAN
50105220	PIPE CULVERT REMOVAL	FOOT	118	118
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	3	3
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1	1
54248510	CONCRETE COLLAR	CU YD	0.62	0.62
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	111	111
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	45	45
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	67	67
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	224	224
67100100	MOBILIZATION	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6

13