

FAU 9760 (US 45) PAVEMENT MARKING SCHEDULE

STATION TO STATION	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING								TEMPORARY				SHORT-TERM PAVT MARK.	NOTES	
	4 INCH (WHITE EDGELINE)	4 INCH (YELLOW SKIP-DASH)	4 INCH (WHITE SKIP-DASH)	4 INCH SOLID YELLOW	4 INCH SOLID WHITE	6 INCH SOLID WHITE	12 INCH (WHITE DIAGONALS)	24 INCH (STOP BARS)	4 INCH	6 INCH	12 INCH	24 INCH			
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT			
FAU 9760 (US 45) - STA. 1060+67 TO STA. 1137+25 (URBAN LIMITS)															
Lt.	1060+67.00	TO	1085+18.00	2451									2451		
Lt.	1060+67.00	TO	1071+33.00				1066						1066		NPZ
Rt.	1060+67.00	TO	1061+82.00				115						115		NPZ
Rt.	1060+67.00	TO	1084+05.00	2338									2338		
	1061+82.00	TO	1081+57.00		494								494		
Rt.	1079+46.00	TO	1083+41.00				395						395		NPZ
Lt.	1081+57.00	TO	1083+41.00				184						184		NPZ
	1083+41.00	TO	1084+92.00				604		40				604	40	Cont. CLTL
	1084+92.00	TO	1110+03.20			1256							1256		Thru Lanes
Lt & Rt.	1084+92.00	TO	1092+40.00		374		1496						1870		Cont. CLTL
Lt & Rt.	1092+40.00	TO	1093+40.00				400		35				400	35	Cont. CLTL
Lt & Rt.	1093+40.00	TO	1094+40.00				200	100					300		LTL Lines
Lt & Rt.	1095+20.00	TO	1105+00.00		490		1960						2450		Cont. CLTL
Lt & Rt.	1105+00.00	TO	1107+00.00				800		85				800	85	Cont. CLTL
Lt & Rt.	1105+00.00	TO	1107+20.00				400		90				400	90	Diagonals
Lt & Rt.	1107+00.00	TO	1109+07.00				414						414		DbI. Yellow
Rt.	1108+60.00	TO	1110+90.00				233		40				233	40	Diagonals
Lt & Rt.	1109+07.00	TO	1110+03.20				385		65				385	65	Cont. CLTL
	1060+67.00	TO	1083+41.00												682
	1083+41.00	TO	1085+00.00												95
	1085+00.00	TO	1110+03.20												3004
Eq. Sta. 1110+03.20 (bk.) = Sta. 1110+00.00 (ah.)															

• FAU 9760 (US 45)

FILE NAME =	USER NAME = mccordkr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAU 9760 PAVEMENT MARKING SCHEDULE	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\pwork\mccordkr\0381606\78424-shit-plan.dgn	DRAWN -	REVISED -	•			40RS-10, 41RS-6	MASSAC	45	15	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 78219							
PLOT DATE = 3/19/2014	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		