

SUMMARY OF QUANTITIES

1123111, 01		1123111, 02	
FAU 9760 (US 45)		FAU 9760 (US 45)	
URBAN		URBAN	
80% FED.; 20% STATE		80% FED.; 20% CITY	
RESURFACING		PARKING LANES	
MASSAC COUNTY			
CONST. CODE TYPE 0005			

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
X4420676	CLASS B PATCHES, TYPE IV, 9 INCH (SPECIAL)	SQ YD	715	715	
X2503100	MOWING	UNITS	50	50	
X4060110	BITUMINOUS MATERIAL (PRIME COAT)	POUND	28478	27267	1211
X7801000	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	765.5	765.5	
X7801004	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24581	24581	
X7801006	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	390	390	
X7801012	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	460	460	
X7801024	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100	100	
40600909	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	1771	1695	76
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	87	87	
40600990	TEMPORARY RAMP	SQ YD	178	178	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXTURE D, N90	TON	3555	3404	151
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	42	42	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL 3/4"	SQ YD	7525	7525	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"	SQ YD	32316	30579	1737
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	266	266	
44201299	DOWELS 1 1/2"	EACH	757	757	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	446	446	
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	103	103	
44213100	PAVEMENT FABRIC	SQ YD	715	715	
44213200	SAW CUTS	FOOT	5064	5064	

* SPECIALTY ITEM
 Non-Participating

FILE NAME :	USER NAME : maoardkr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
at:\work\p\1\dat\mccardkr\031626\784	04-ht-plan.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	Illinois	29	5
	PLOT SCALE = 1/8" = 1' / in.	CHECKED -	REVISED -						41RS-7	Massac			
	PLOT DATE = 3/19/2014	DATE -	REVISED -						CONTRACT NO. 78404		ILLINOIS FED. AID PROJECT		

FAU 9760 (US 45)