

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING						SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING						REMARKS
	LINE 4"			LINE 12" - WHITE SOLID	LINE 24" - WHITE SOLID	LETTERS & SYMBOLS			LINE 4"			LINE 12" - WHITE SOLID	LINE 24" - WHITE SOLID	LETTERS & SYMBOLS	
	WHITE	YELLOW							WHITE	YELLOW					
	SOLID	SOLID	SKIP DASH						SOLID	SOLID	SKIP DASH				
FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT		
ILLINOIS 14 (FAP 869)															
MAINLINE															
907+06. TO 907+37.		124					16.0	44.0		124.0				2-DOUBLE YELLOW	
907+37. TO 909+78.		482	120.0				80.0	214.0		482.0	120.0			TWLT LANE	
908+89.						17.6		17.6					17.6	TWLT ARROWS	
909+78. TO 910+32.69 BK		218.76					16.0	75.6		218.8				2-DOUBLE YELLOW	
910+32.69 BK TO 869+71.5 AH															
869+71.5 AH TO 869+94.		90					16.0	32.7		90.0				2-DOUBLE YELLOW	
870+27.						20.8		20.8					20.8	"ONLY"	
870+51.						8.8		8.8					8.8	LEFT ARROW	
869+94. TO 870+61. LT		134					32.0	50.0		134.0				DOUBLE YELLOW	
869+94. TO 870+71. RT	77.0						32.0	31.0	77.0						
870+61.						10.0		20.0				10.0		STOP BAR	
870+71.						17.0		34.0				17.0		STOP BAR	
870+71. TO 871+40.														DU QUOIN ST.	
871+40.						17.0		34.0				17.0		STOP BAR	
871+40. TO 872+09. LT	69.0						32.0	28.3	69.0						
871+50.						10.0		20.0				10.0		STOP BAR	
871+50. TO 872+09. RT		118					16.0	42.0		118.0				DOUBLE YELLOW	
871+75.						8.8		8.8					8.8	LEFT ARROW	
871+89.						20.8		20.8					20.8	"ONLY"	
872+09. TO 872+87.		312					32.0	109.3		312.0				2-DOUBLE YELLOW	
872+87. TO 889+70.		3,366	840.0				608.0	1503.3		3366.0	840.0			TWLT LANE	
874+14.						17.6		17.6					17.6	TWLT ARROWS	
876+26.						17.6		17.6					17.6	TWLT ARROWS	
878+34.						17.6		17.6					17.6	TWLT ARROWS	
880+43.						17.6		17.6					17.6	TWLT ARROWS	
882+51.						17.6		17.6					17.6	TWLT ARROWS	
884+60.						17.6		17.6					17.6	TWLT ARROWS	
886+71.				66.0				66.0				66.0		CROSS WALK	
886+86.						17.6		17.6					17.6	TWLT ARROWS	
889+35.						17.6		17.6					17.6	TWLT ARROWS	
889+70. TO 889+75.				66.0				66.0				66.0		CROSS WALK	
889+75. TO 890+49.														MAPLE ST.	
890+49. TO 890+54.				66.0				66.0				66.0		CROSS WALK	
890+54. TO 891+16. LT	62.0						16.0	23.3	62.0						
890+54. TO 891+16. RT		124								124.0				DOUBLE YELLOW	
890+88.						8.8		8.8					8.8	LEFT ARROW	
891+05.						20.8		20.8					20.8	"ONLY"	
891+16. TO 892+21.		420					32.0	145.3		420.0				2-DOUBLE YELLOW	
893+13				66.0								66.0		CROSSWALK	
TOTAL	208	5,389	960	264	54	247	928	2,852	208	5,389	960	264	54	247	

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	P.A. RTE. 869	SECTION 4RS-4	COUNTY FRANKLIN	TOTAL SHEETS 11	SHEET NO. 9	
FILE#		DRAWN -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.					
#MODELNAME*		CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT					
		DATE -	REVISED -			CONTRACT NO. 78412					