



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 30, 2014

SUBJECT: FAS 883 (CH 14)  
Project RS-0883(115)  
Section 99-00087-00-RS  
Hamilton County  
Contract No. 99529  
Item 198  
June 13, 2014 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

### **1. Page 6 of Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

Method of Measurement

The Portland Cement Concrete Overlay, 4" will be measured for payment in accordance with Article 420.19. The Portland Cement Concrete Pavement, Furnished will be computed in cubic yards. Additional material required due to irregularities in the existing pavement exceeding the amount computed for the Portland Cement Concrete Pavement, Furnished will be paid for in accordance with Article 109.05. The volume of the additional material will be determined by subtracting the computed volume of the overlay from the ticketed volume of the overlay delivered. If for any reason the entire truck is not incorporated into the overlay, the Engineer will estimate the quantity remaining in the truck and subtract this volume from the delivered total.

Basis of Payment

The work for portland cement concrete pavement furnished will include the cost of furnishing all Class PV concrete with the appropriate amount of synthetic fibers and transportation to the jobsite. This work will be paid for at the contract unit price per cubic yard for PORTLAND CEMENT CONCETE PAVEMENT, FURNISHED. The work for portland cement concrete overlay placement will include the costs associated with placement, finishing, curing, reinforcing and sawing in accordance with the plans and specifications. This work will be paid for at the contract unit price per square yard for PORTLAND CEMENT CONCRETE OVERLAY 4", which price shall include placement of variable depth overlay where the new concrete overlay abuts the east side of Structure #033-3224, both sides of Structure #033-3010 and at the end of the project. The work for portland cement concrete pavement 8" placement associated with the private entrances and township road intersections will be paid for at the contract unit price per square yard for PORTLAND CEMENT CONCRETE PAVEMENT, 8" PLACEMENT.

**PRIVATE ENTRANCE AND INTERSECTION CROSSINGS**

The Contractor shall make sure local residents are aware of their paving schedule and make necessary arrangements for their access. The arrangements may include but are not limited to parking on the other side of the road, placing a temporary entrance for parking or leaving a gap in the pavement for resident ingress and egress. All work associated with these processes shall be included in the cost of the PORTLAND CEMENT CONCRETE PAVEMENT, 8" PLACEMENT.

**AGGREGATE SURFACE COURSE, TYPE B**

This work shall consist of all labor, material and equipment necessary to make a smooth transition from the new construction to the existing grade height at all private entrances and field entrances. This work shall conform to all applicable articles of Section 402 of the Standard Specifications. In addition to conforming to Section 402 of the Standard Specifications, the Aggregate Surface Course, Type B shall be crushed stone. All work associated with these processes shall be included in the contract unit price per ton for AGGREGATE SURFACE COURSE, TYPE B.