	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE A 0003 URBAN	B 0040 URBAN	C 0040 URBAN	D 0040 URBAN	E 0040 URBAN	F 0010 URBAN	G 0010 URBAN	H 0021 URBAN	I 0021 URBAN	J 0021 URBAN	K 0021 URBAN	L 0028 URBAN	M 0028 URBAN	N 0003 URBAN	O 0003 URBAN
X	81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	330	B									330	B				
X	81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	1174									1174						
X	81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	4							2	4							
X	81300830	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 8"	EACH	12	B								8	4	B				
X	81400100	HANDHOLE	EACH	16									16						
X	81400200	HEAVY-DUTY HANDHOLE	EACH	5									5						
X	81400300	DOUBLE HANDHOLE	EACH	14									14						
X	81603030	UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	508								508							
X	81603090	UNIT DUCT, 600V, 3-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	3241								3241							
X	81603136	UNIT DUCT, 600V, 5-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	1385								1385							
X	81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	640								640							
X	81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	2560								2560							
~~X~~	~~81702180~~	~~ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0~~	~~FOOT~~	~~120~~								120	A						

X SPECIALTY ITEM

A ROADWAY AND DRAINAGE - 100% STATE
B RETAINING WALL SN 022-W063 - 100% STATE
C RETAINING WALL SN 022-W064 - 100% STATE
D RETAINING WALL SN 022-W065 - 100% STATE
E RETAINING WALL SN 022-W066 - 100% STATE
F BRIDGE SN 022-2029 - 100% STATE
G BRIDGE SN 022-2030 - 100% STATE

H LIGHTING - 100% STATE
I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE
J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE
K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE
L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE

M SHARED-USE PATH - 100% NAPERVILLE
N ROADWAY ITEMS - 100% STATE
O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

B Rev. 6-5-13
A Rev. 1-3-13

FILE NAME =	USER NAME =	DESIGNED PJO	REVISED
		DRAWN KFS	REVISED
	PLOT SCALE =	CHECKED JCM	REVISED
	PLOT DATE =	DATE 10/15/2012	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 21 OF 41 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-5	DUPAGE	963	26
		CONTRACT NO. 60131		
	ILLINOIS FED. AID PROJECT			