

| HOT-MIX ASPHALT SHOULDERS (6 IN.) | | | |
|-----------------------------------|---------|-------|----------------|
| FROM | TO | LT/RT | QUANTITY SQ YD |
| 1001+43 | 1002+00 | RT | 48 |
| 1002+00 | 1022+51 | RT | 2276 |
| 1003+56 | 1004+56 | LT | 31 |
| 1004+56 | 1012+85 | LT | 371 |
| 1022+51 | 1023+51 | RT | 118 |
| 1023+51 | 1028+55 | RT | 560 |
| 1028+55 | 1029+05 | RT | 58 |
| 1029+05 | 1041+02 | RT | 1463 |
| 1041+02 | 1041+55 | RT | 79 |
| 1986+78 | 1987+82 | RT | 120 |
| 1986+78 | 1996+00 | LT | 414 |
| 1987+82 | 1998+15 | RT | 1144 |
| 1996+00 | 1997+50 | LT | 46 |
| 1998+15 | 1998+57 | RT | 30 |
| 6526+45 | 6528+41 | RT | 240 |
| 6526+56 | 6528+72 | RT | 310 |
| 6526+56 | 6528+72 | LT | 320 |
| 6526+68 | 6528+70 | LT | 245 |
| 7001+23 | 7001+58 | RT | 30 |
| 7001+68 | 7002+84 | LT | 34 |
| 7001+58 | 7014+73 | RT | 1479 |
| 7002+84 | 7013+71 | LT | 483 |
| 7013+71 | 7014+73 | LT | 51 |
| 8959+48 | 8959+99 | RT | 68 |
| 8959+99 | 8966+56 | RT | 802 |
| 8966+56 | 8967+53 | RT | 145 |
| 8990+83 | 8996+64 | LT | 264 |
| 8996+64 | 8997+31 | LT | 21 |
| 8996+64 | 8998+29 | RT | 183 |
| 8998+29 | 8998+71 | RT | 35 |
| PROJECT TOTAL | | | 11471 |

| CONCRETE BARRIER DELINEATOR, REFLECTOR MARKER TYPE C | | | | |
|--|---------|----------|----------------|---------------|
| FROM | TO | LT/CT/RT | DESCRIPTION | QUANTITY EACH |
| EXISTING | | | | |
| 6498+00 | 6579+00 | CT | EX 1-88 MEDIAN | 81 |
| 6498+00 | 6579+00 | CT | EX 1-88 MEDIAN | 81 |
| EXISTING SUBTOTAL | | | | 162 |
| STAGE 1 | | | | |
| 1986+00 | 1999+76 | RT | RAMP D | 14 |
| 1988+80 | 1999+05 | LT | RAMP D | 11 |
| 1001+15 | 1003+03 | RT | RAMP A | 2 |
| 1001+45 | 1012+00 | LT | RAMP A | 11 |
| 1010+00 | 1015+89 | RT | RAMP A | 6 |
| 8990+88 | 8999+34 | LT | RAMP B | 9 |
| 7001+40 | 7007+59 | RT | RAMP C | 7 |
| 7001+40 | 7010+17 | LT | RAMP C | 9 |
| 6560+30 | 6561+25 | CT | I-88 | 1 |
| STAGE 1 SUBTOTAL | | | | 70 |
| STAGE 1A | | | | |
| 6519+92 | 6532+42 | RT | I-88 | 13 |
| 6523+08 | 6535+33 | LT | I-88 | 13 |
| STAGE 1A SUBTOTAL | | | | 26 |
| PERMANENT | | | | |
| 1012+55 | 1013+57 | RT | RAMP A RW | 2 |
| PERMANENT SUBTOTAL | | | | 2 |
| PROJECT TOTAL | | | | 260 |

| CONCRETE MEDIAN BARRIER AND BASE REMOVAL | | | |
|--|---------|-----------|---------------|
| FROM | TO | LT/CTR/RT | QUANTITY FOOT |
| 6526+56 | 6527+12 | CTR | 58 |
| 6526+69 | 6527+00 | RT | 31 |
| 6527+84 | 6528+72 | CTR | 88 |
| 6527+95 | 6528+25 | LT | 31 |
| PROJECT TOTAL | | | 208 |

| RIGHT-OF-WAY FENCE TYPE 1, 6' | | | |
|-------------------------------|---------|-------|---------------|
| FROM | TO | LT/RT | QUANTITY FOOT |
| 1001+53 | 1005+04 | RT | 400 |
| PROJECT TOTAL | | | 400 |

| FROM | TO | LT/MED/RT | CONCRETE MEDIAN BARRIER TRANSITION, TYPE V-F | CONCRETE BARRIER BASE (SPECIAL) |
|---------------|---------|-------------|--|---------------------------------|
| | | | FOOT | FOOT |
| 6526+56 | 6526+86 | I-88 MEDIAN | 30 | 30 |
| 6527+44 | 6527+90 | I-88 MEDIAN | 47 | 47 |
| 6528+42 | 6528+72 | I-88 MEDIAN | 30 | 30 |
| PROJECT TOTAL | | | 107 | 107 |