





STAGE 3B TEMPORARY TRAFFIC SIGNALS




SEE SHEET TS-13 FOR STAGE 3B TEMPORARY CABLE PLAN

RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.


THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

LEGEND

-  CONSTRUCTION WORK ZONE
-  TEMPORARY PAVEMENT PLACED IN THIS STAGE
-  DIRECTION OF TRAFFIC
-  VIDEO DETECTION ZONE

-  R3-2
36" x 36"
1 REQUIRED
-  R3-1
36" x 36"
1 REQUIRED
-  R10-5
30" x 36"
1 REQUIRED

INCIDENTAL TO TEMPORARY TRAFFIC SIGNAL INSTALLATION



FILE NAME	USER NAME - RUSERS	DESIGNED <i>MJM</i>	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY TRAFFIC SIGNAL INSTALLATION MOT STAGES 3B IL ROUTE 59 AND I-88 NORTH RAMPS			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4FILEL6		DRAWN <i>KES</i>	REVISED		338	(112 & 113) WRS-5	DUPAGE	963	427			
		CHECKED <i>JCM</i>	REVISED		TS-12				CONTRACT NO. 60131			
		DATE <i>10/15/2012</i>	REVISED		ILLINOIS FED. AID PROJECT							
				SCALE: AS SHOWN	SHEET NO. 12 OF 53 SHEETS	STA.	TO STA.					