FOR CONTINUATION OF IMPROVEMENT
SEE DIEHL ROAD
PLAN-PROFILE SHEET

STA. 4041+23.18 ILLINOIS ROUTE 59 =
STA. 100+00.00 DIEHL RD.

DIEHL ROAD

EXISTING R.O.W.
PROPOSED R.O.W.

RB-29

MATCH LINE STA. 4036+50

RW-51
RW-52
RW-53

PROPOSED R.O.W.
PROPOSED RETAINING WALL
EXISTING R.O.W.

RB-75

DIEHL ROAD

~ PROPOSED ℄ RTE 59

RB-30

100+00

PROPOSED R.O.W.
EXISTING R.O.W.

ILLINOIS ROUTE 59

RB-32

MATCH LINE STA. 4050+00

RB-31

PROPOSED R.O.W.

EXISTING R.O.W.

N

HORIZONTAL SCALE: 1"=50'-0"

VERTICAL SCALE: 1"=5'-0"

(10) 1.0'-2.5' CLAY LOAM (A-6) LL=31 PL=17 PI=14 G.I.=8

~ DIEHL ROAD STA. 4041+23.18

RB-29 4037+00 72.0' Left 709.5

	N	Qu	W%
TOPSOIL AS	-	-	25
CLAY LOAM FILL (A-6)	7	2.25P	19
SILTY CLAY (A-6)	9	2.0P	23
SILTY CLAY LOAM (A-4/A-6)	10	1.5P	25
CLAY (A-6)	13	6.6B	19
EOB			

RW-51 4038+21 83.5' Right 707.9

	N	Qu	W%
TOPSOIL AS	-	-	33
SAND & GRAVEL (FILL)	10	NP	9
CLAY LOAM (A-6)	17	4.75B	20
	12	2.0B	14
SAND & GRAVEL (A-1)	9	NP	8
	12	NP	17
CLAY LOAM (A-4/A-6)	21	2.1B	12
	10	1.0P	12
	12	1.0P	10
EOB			

RB-30 4043+00 48.5' Left 707.3

	N	Qu	W%
TOPSOIL AS	-	-	21
	10	4.1S	14
CLAY LOAM (A-6)	13	6.4B	16
	12	4.5P	13
	11	5.6B	16
	12	3.7B	18
CLAY (A-6)	14	4.25B	18
	13	2.8B	20
	11	1.7B	22
EOB			

RB-31 4046+00 45.0' Right 708.3

	N	Qu	W%
TOPSOIL AS	-	-	21
SILTY CLAY (A-6)	10	3.0P	29
	15	4.5+P	14
CLAY (A-6)	18	2.9B	16
	22	7.2B	15
EOB			

RB-32 4049+00 36.5' Left 709.9

	N	Qu	W%
TOPSOIL AS	-	-	21
CLAY LOAM FILL (A-6)	4	4.0P	12
	16	4.25P	16
	16	4.9B	16
CLAY (A-6)	20	6.2B	15
	31	10.4B	17
	21	4.8B	16
	11	3.9B	13
SILTY CLAY LOAM (A-4/A-6)	18	NP	12
EOB			

715 710 705 700 695 690 685

709.40 709.59 709.67 709.60 709.43 709.25 709.08 708.90 708.73 708.55 708.38 708.20 708.03 707.85 707.68 707.50 707.33 707.15 706.98 706.94 707.00 707.25 707.65 708.21 708.92 709.79 710.81 711.99

4037+00 4038+00 4039+00 4040+00 4041+00 4042+00 4043+00 4044+00 4045+00 4046+00 4047+00 4048+00 4049+00 4050+00

Geo Services, Inc. Geotechnical, Environmental & Civil Engineering 805 Amherst Court, Suite 204 Naperville, Illinois 60563 (630) 305-2838	USER NAME =	DESIGNED - RWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SOIL BORING PLAN / PROFILE ILLINOIS ROUTE 59
		DRAWN - RWC	REVISED -		
	PLOT SCALE =	CHECKED - AJP	REVISED -		
	PLOT DATE =	DATE - 3/24/2011	REVISED -		

SCALE: | SHEET NO. OF SHEETS | STA. 4036+50 TO STA. 4050+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338/IL 59	(82 & 83) WRS-5	DUPAGE	963	689
		CONTRACT NO. 60131		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT