PRE-STAGE 1		UNIT
EARTH EXCAVATION	19.2	SQ FT.
EMBANKMENT	86.9	SQ FT.
TOPSOIL EXC & PLAC	56.6	SQ FT.

NB - 931+74.8
CL - 4069+50
SB - 831+88.1

PRE-STAGE 1		UNIT
EARTH EXCAVATION	21.2	SQ FT.
EMBANKMENT	94.1	SQ FT.
TOPSOIL EXC & PLAC	59.8	SQ FT.

NB - 931+24.8
CL - 4069+00
SB - 831+38.14

PRE-STAGE 1		UNIT
EARTH EXCAVATION	20.2	SQ FT.
EMBANKMENT	128.1	SQ FT.
TOPSOIL EXC & PLAC	62.9	SQ FT.

NB - 930+74.8
CL - 4068+50
SB - 830+88.1

NOTE:
A DEPTH OF 12 INCHES IS USED IN THE TOPSOIL EXCAVATION AND PLACEMENT CALCULATION.

LEGEND:
TEMPORARY PAVEMENT

FILE NAME = $FILE$	USER NAME = $USER$	DESIGNED - RIA	REVISED -
		DRAWN - KES	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - PJO	REVISED -
	PLOT DATE = $DATE$	DATE - 10/15/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CROSS-SECTIONS
ILLINOIS ROUTE 59 - PRE-STAGE

SCALE: | SHEET NO. 23 OF 30 SHEETS | STA. 4068+50 | TO STA. 4069+50

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-5	DUPAGE	963	758
		CONTRACT NO. 60131		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		