URBAN
90% FED.
10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				ROADWAY 0004 URBAN	BRIDGE 0011 SN 016-2439	BRIDGE 0011 SN 016-2440	BRIDGE 0014 SN 016-2441	BRIDGE 0014 SN 016-2442	BRIDGE 0011 SN 016-2470	BRIDGE 0011 SN 016-2471	SAFETY 0021 URBAN
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,979	1,979							
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX F, N90	TON	4,617	4,617							
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	4,787	4,787							
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	22,340	22,340							
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	121	121							
44000100	PAVEMENT REMOVAL	SQ YD	42,440	42,440							
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	45,029	45,029							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	772	772							
44001980	CONCRETE BARRIER REMOVAL	FOOT	3,865	3,865							
44004250	PAVED SHOULDER REMOVAL	SQ YD	31,548	31,548							
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	5,383	5,383							
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	7,184	7,184							
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	1,896	1,896							

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

FILE NAME = #FILEL#	USER NAME = default	DESIGNED -	REVISED -
		DRAWN - QC	REVISED -
	PLOT SCALE = $SCALE$	CHECKED - RGR	REVISED -
	PLOT DATE = 4/4/2013	DATE - 03/29/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA | SHEET NO. 3 OF 24 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	5

CONTRACT NO. 60J12
ILLINOIS FED. AID PROJECT

S:\0272\05_CADD\016B312 Sheets\016B312-sht-sesu.dgn