

URBAN
90% FED.
10% STATE

CONSTRUCTION CODE

| CODE NO | ITEM | UNIT | TOTAL QUANTITY | ROADWAY 0004 URBAN | BRIDGE 0011 SN 016-2439 | BRIDGE 0011 SN 016-2440 | BRIDGE 0014 SN 016-2441 | BRIDGE 0014 SN 016-2442 | BRIDGE 0011 SN 016-2470 | BRIDGE 0011 SN 016-2471 | SAFETY 0021 URBAN |
|----------|---|-------|----------------|--------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------|
| 50500105 | FURNISHING AND ERECTING STRUCTURAL STEEL | L SUM | 1 | | | | 0.10 | | | 0.45 | 0.45 |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 25,977 | | | | 13,572 | | | 7,728 | 4,677 |
| 50800105 | REINFORCEMENT BARS | POUND | 156 | 156 | | | | | | | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 804,410 | | | | 385,470 | 53,295 | 53,295 | 175,210 | 137,140 |
| 50800515 | BAR SPLICERS | EACH | 5,124 | | | | 1,691 | | | 2,318 | 1,115 |
| 51100100 | SLOPE WALL 4 INCH | SO YD | 99 | | | | 99 | | | | |
| 51200957 | FURNISHING METAL SHELL PILES 12" X 0.250" | FOOT | 4,772 | | | | | | | 2,354 | 2,418 |
| 51200959 | FURNISHING METAL SHELL PILES 14" X 0.312" | FOOT | 1,400 | | | | | | | 1,400 | |
| 51202305 | DRIVING PILES | FOOT | 6,172 | | | | | | | 3,754 | 2,418 |
| 51203200 | TEST PILE METAL SHELLS | EACH | 6 | | | | | | | 3 | 3 |
| 51500100 | NAME PLATES | EACH | 3 | | | | 1 | | | 1 | 1 |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 650 | | | | 184 | 108 | 108 | 138 | 112 |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 24 | | | | | | | 12 | 12 |
| 52100020 | ELASTOMERIC BEARING ASSEMBLY, TYPE II | EACH | 26 | | | | 26 | | | | |

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.226.0100
www.bbandainc.com



| | | | |
|-----------|-----------|-------------------|-----------|
| FILE NAME | USER NAME | DESIGNED | REVISED |
| *FILE* | default | DRAWN - OC | REVISED - |
| | | CHECKED - RGR | REVISED - |
| | | DATE - 03/29/2013 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 5 OF 24 SHEETS STA. TO STA.

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------|-------------|--------|---------------------------|-----------|
| 94 | 2012-059-BR | COOK | 631 | 7 |
| CONTRACT NO. 60J12 | | | ILLINOIS FED. AID PROJECT | |

5/10/2005 COOK/D168112 Sheet 11 of 24