

URBAN  
90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004 URBAN	BRIDGE 0011 SN 016-2439	BRIDGE 0011 SN 016-2440	BRIDGE 0014 SN 016-2441	BRIDGE 0014 SN 016-2442	BRIDGE 0011 SN 016-2470	BRIDGE 0011 SN 016-2471	SAFETY 0021 URBAN
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2							
60260100	INLETS TO BE ADJUSTED	EACH	1	1							
60270050	DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20 FRAME AND GRATES	EACH	16	16							
60270055	DRAINAGE STRUCTURES, TYPE 5 WITH TWO TYPE 22 FRAME AND GRATES	EACH	3	3							
60500040	REMOVING MANHOLES	EACH	3	3							
60500050	REMOVING CATCH BASINS	EACH	29	29							
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3							
60600605	CONCRETE CURB, TYPE B	FOOT	634	634							
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	105	105							
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	303	303							
60900515	CONCRETE THRUST BLOCKS	EACH	2	2							
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	2	2							
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	3,963	3,963							
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7	7							

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



FILE NAME *	USER NAME * default	DESIGNED -	REVISED -
#FILE#		DRAWN - OC	REVISED -
	PLOT SCALE * 4/4/2013	CHECKED - RGR	REVISED -
		DATE - 03/29/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 8 OF 24 SHEETS STA. TO STA.

F.A.I. RTE. 94	SECTION 2012-059-BR	COUNTY COOK	TOTAL SHEETS 631	SHEET NO. 10
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60J12	

\*Specialty Items