

URBAN
90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0004 URBAN	BRIDGE 0011 SN 016-2439	BRIDGE 0011 SN 016-2440	BRIDGE 0014 SN 016-2441	BRIDGE 0014 SN 016-2442	BRIDGE 0011 SN 016-2470	BRIDGE 0011 SN 016-2471	SAFETY 0021 URBAN
*83050825	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. DAVIT ARM	EACH	137								137
*83050945	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 2-10 FT. DAVIT ARMS	EACH	17								17
*83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	53								53
*83057475	LIGHT POLE, WOOD, 90 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	2								2
*83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	1,463								1,463
*83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	137								137
*84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	70								70
*84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	152								152
*84200804	REMOVAL OF POLE FOUNDATION	EACH	152								152
*84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	8								8
*84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2								2
*84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	3								3
*87000885	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (XLP-TYPE TC) 2/C NO. 6 AND NO. 8	FOOT	2000								2000
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4,600								4,600
*87800200	CONCRETE FOUNDATION, TYPE D	FOOT	16								16

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



FILE NAME *	USER NAME * default	DESIGNED -	REVISED -
#FILE#		DRAWN - OC	REVISED -
	PLOT SCALE * #SCALE#	CHECKED - RCR	REVISED -
	PLOT DATE * 4/4/2013	DATE - 03/29/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 15 OF 24 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	17
			CONTRACT NO. 60J12	
ILLINOIS FED. AID PROJECT				

*Specialty Items Rev.

S:\2012\059\060J12_Sheet 15 of 24.dwg