

EX LINE D			STAGE 1					STAGE 2						
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
STATION			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
60+64.84	TO	61+00.00	6.22	5.29	0.14	5.15	0.00	0.00	11.85	10.07	5.03	5.05	16.96	6.78
61+00.00	TO	62+00.00	33.61	28.57	2.11	26.46	7.07	1.39	60.04	51.03	25.06	25.98	70.76	25.07
62+00.00	TO	63+00.00	31.02	26.37	3.96	22.40	14.26	3.13	50.93	43.29	30.70	12.58	64.74	18.91
63+00.00	TO	64+00.00	15.09	12.83	2.24	10.59	7.19	1.74	64.59	54.90	18.20	36.70	50.65	13.09
64+00.00	TO	65+00.00	0.00	0.00	0.00	0.00	0.00	0.00	79.31	67.42	4.15	63.27	31.41	5.04
65+00.00	TO	66+00.00	0.00	0.00	0.00	0.00	0.00	0.00	75.44	64.13	11.56	52.57	42.52	9.94
66+00.00	TO	67+00.00	0.00	0.00	0.00	0.00	0.00	0.00	71.74	60.98	18.07	42.91	48.22	13.44
67+00.00	TO	68+00.00	0.00	0.00	0.00	0.00	0.00	0.00	70.74	60.13	15.52	44.61	44.69	11.65
68+00.00	TO	69+00.00	0.00	0.00	0.00	0.00	0.00	0.00	67.50	57.38	17.22	40.15	40.13	12.96
69+00.00	TO	70+00.00	15.09	12.83	8.74	4.09	0.00	9.26	47.37	40.26	11.43	28.84	19.57	8.02
70+00.00	TO	71+00.00	30.93	26.29	18.80	7.49	0.00	16.63	59.50	50.58	0.00	50.58	0.00	0.00
71+00.00	TO	71+48.56	32.41	27.55	12.54	15.00	0.00	9.04	47.07	40.01	0.17	39.84	0.00	0.00
71+48.56	TO	72+00.00	46.88	39.85	20.80	19.04	0.00	10.88	47.31	40.21	0.36	39.85	0.00	0.00
72+00.00	TO	72+53.42	51.30	43.61	18.21	25.40	0.51	8.55	29.26	24.87	0.19	24.68	0.00	0.00
72+53.42	TO	73+00.00	52.90	44.97	9.73	35.24	2.93	5.37	14.34	12.19	0.00	12.19	0.00	0.00
73+00.00	TO	74+00.00	130.72	111.11	18.37	92.74	12.50	7.54	15.43	13.11	0.00	13.11	0.00	0.00
74+00.00	TO	75+00.00	154.39	131.23	10.70	120.53	19.85	5.28	0.00	0.00	0.00	0.00	0.00	0.00
75+00.00	TO	76+00.00	126.41	107.45	3.80	103.65	12.69	3.19	15.80	13.43	0.00	13.43	3.93	0.52
76+00.00	TO	77+00.00	86.63	73.64	0.00	73.64	0.00	0.00	32.61	27.72	0.00	27.72	5.89	0.52
77+00.00	TO	78+00.00	82.94	70.50	0.15	70.35	0.00	0.00	33.15	28.18	3.48	24.69	15.44	3.33
78+00.00	TO	79+00.00	83.44	70.93	0.15	70.78	0.00	0.00	35.65	30.30	10.22	20.08	13.48	11.74
79+00.00	TO	80+00.00	82.98	70.53	0.00	70.53	0.00	0.00	39.13	33.26	20.89	12.37	10.15	23.94
80+00.00	TO	80+74.82	61.23	52.04	0.00	52.04	0.00	0.00	29.55	25.12	27.72	-2.60	16.68	30.80

EX RAMP R			STAGE 1					STAGE 2						
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
STATION			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
611+47.60	TO	612+00.00	0.11	0.09	7.97	-7.88	4.06	9.71	0.00	0.00	0.00	0.00	0.00	0.00
612+00.00	TO	613+00.00	0.00	0.00	12.06	-12.06	5.48	11.72	0.00	0.00	0.00	0.00	0.00	0.00
613+00.00	TO	613+13.29	0.00	0.00	0.79	-0.79	0.51	0.60	0.00	0.00	0.00	0.00	0.00	0.00

PR LINE D			STAGE 1					STAGE 2						
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
STATION			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
080+74.82	TO	081+00.00	48.69	41.39	0.00	41.39	0.00	0.00	32.87	27.94	10.20	17.74	4.72	10.99
081+00.00	TO	082+00.00	180.52	153.44	0.00	153.44	0.00	0.00	115.17	97.89	44.94	52.95	7.80	49.65
082+00.00	TO	083+00.00	184.07	156.46	0.00	156.46	0.00	0.00	94.81	80.59	52.94	27.65	1.91	68.31
083+00.00	TO	084+00.00	195.69	166.33	0.00	166.33	0.00	0.00	83.17	70.69	52.41	18.28	0.00	77.33
084+00.00	TO	085+00.00	191.67	162.92	1.69	161.23	0.00	0.00	82.22	69.89	47.52	22.37	0.00	79.57
085+00.00	TO	086+00.00	194.80	165.58	15.44	150.13	0.00	27.50	84.54	71.86	46.13	25.73	0.00	67.48
086+00.00	TO	087+00.00	208.67	177.37	27.67	149.70	0.00	55.31	88.59	75.30	34.89	40.41	0.00	51.80
087+00.00	TO	088+00.00	199.56	169.62	13.91	155.71	0.00	27.81	90.15	76.63	20.80	55.83	0.00	51.54
088+00.00	TO	089+00.00	179.46	152.54	0.00	152.54	0.00	0.00	84.17	71.54	26.44	45.10	0.00	55.13
089+00.00	TO	090+00.00	169.15	143.78	0.00	143.78	0.00	0.00	79.78	67.81	53.06	14.76	0.00	63.28
090+00.00	TO	091+00.00	154.28	131.14	0.00	131.14	0.00	0.00	80.17	68.14	62.70	5.44	15.50	66.72
091+00.00	TO	092+00.00	185.98	158.08	0.00	158.08	0.00	0.00	79.50	67.58	42.15	25.43	48.56	50.67
092+00.00	TO	093+00.00	228.83	194.51	0.00	194.51	0.00	0.00	96.30	81.85	20.80	61.06	72.96	32.69
093+00.00	TO	094+00.00	196.02	166.62	0.00	166.62	0.00	0.00	114.89	97.66	9.07	88.58	39.91	18.31
094+00.00	TO	095+00.00	176.11	149.69	0.00	149.69	0.00	0.00	271.30	230.60	12.70	217.90	0.00	40.72
095+00.00	TO	096+00.00	201.59	171.35	0.00	171.35	0.00	0.00	339.09	288.23	32.81	255.41	0.00	80.80
096+00.00	TO	097+00.00	209.22	177.84	0.00	177.84	0.00	0.00	199.44	169.53	25.80	143.73	38.33	61.76
097+00.00	TO	098+00.00	186.39	158.43	0.00	158.43	0.00	0.00	146.26	124.32	4.89	119.43	67.80	35.19
098+00.00	TO	099+00.00	147.72	125.56	0.00	125.56	0.00	0.00	121.85	103.57	4.39	99.19	78.74	30.28
099+00.00	TO	100+00.00	117.00	99.45	0.00	99.45	0.00	0.00	86.09	73.18	5.57	67.60	49.28	15.76
100+00.00	TO	101+00.00	120.76	102.65	0.00	102.65	0.00	0.00	84.69	71.98	5.94	66.04	0.00	5.09
101+00.00	TO	102+00.00	89.57	76.14	0.00	76.14	0.00	0.00	73.48	62.46	5.06	57.40	0.00	5.11
102+00.00	TO	103+00.00	44.09	37.48	0.00	37.48	0.00	0.00	52.78	44.86	3.37	41.49	0.00	5.11
103+00.00	TO	104+00.00	44.78	38.06	0.00	38.06	0.00	0.00	38.24	32.50	8.44	24.06	0.00	9.80
104+00.00	TO	105+00.00	45.83	38.96	0.00	38.96	0.00	0.00	16.80	14.28	14.19	0.09	0.00	14.57

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbadainc.com



FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
#FILE#		DRAWN - BC	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 03/29/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EARTHWORK SCHEDULE

SCALE: NA SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	34
CONTRACT NO. 60J12			ILLINOIS FED. AID PROJECT	