

MOD LINE E			STAGE 1					STAGE 2						
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
STATION			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
812+30.00	TO	813+00.00	68.92	58.59	5.55	53.04	5.43	1.01	61.50	52.27	15.35	36.92	23.49	7.88
813+00.00	TO	814+00.00	93.39	79.38	12.56	66.83	14.30	3.81	85.96	73.07	16.91	56.16	24.43	8.46
814+00.00	TO	815+00.00	60.80	51.68	57.35	-5.68	53.52	22.02	63.20	53.72	109.67	-55.94	56.39	26.00
815+00.00	TO	815+50.35	15.21	12.93	62.31	-49.39	54.94	23.43	20.49	17.42	261.56	-244.14	59.11	29.12
815+50.35	TO	820+09.45	0.00	0.00	1,002.39	-1,002.39	85.79	42.90	0.00	0.00	957.75	-957.75	184.28	92.14
820+09.45	TO	821+00.00	7.63	6.49	586.16	-579.68	139.11	57.10	4.09	3.48	56.91	-53.43	42.16	12.38
821+00.00	TO	822+00.00	9.31	7.92	128.85	-120.93	88.02	33.04	6.96	5.92	57.41	-51.49	39.54	12.50
822+00.00	TO	823+00.00	28.41	24.15	40.19	-16.04	28.69	9.63	26.06	22.15	18.81	3.33	27.31	6.96
823+00.00	TO	824+00.00	56.80	48.28	25.94	22.33	26.98	8.61	55.81	47.44	7.70	39.74	17.69	3.43
824+00.00	TO	824+20.00	15.49	13.17	5.41	7.75	6.03	2.06	15.07	12.81	1.28	11.53	2.63	0.29

PR LINE F			STAGE 1					STAGE 2						
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
STATION			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
921+61.50	TO	922+00.00	53.28	45.29	12.42	32.87	0.00	5.46	106.18	90.25	4.27	85.98	0.00	1.43
922+00.00	TO	923+00.00	162.19	137.86	27.22	110.64	0.00	13.04	249.19	211.81	14.52	197.29	0.00	5.37
923+00.00	TO	924+00.00	169.87	144.39	23.76	120.63	0.00	11.50	231.48	196.76	15.31	181.44	0.00	7.13
924+00.00	TO	925+00.00	160.83	136.71	22.70	114.00	9.70	10.04	210.76	179.15	85.11	94.03	76.44	46.15
925+00.00	TO	925+97.53	77.39	65.78	653.94	-588.16	9.46	34.79	92.83	78.91	755.69	-676.79	74.56	70.19
925+97.53	TO	926+46.42	0.00	0.00	766.41	-766.41	0.00	30.45	0.00	0.00	807.03	-807.03	0.00	29.74
926+46.42	TO	927+04.19	0.00	0.00	1,055.95	-1,055.95	0.00	36.05	0.00	0.00	1,114.03	-1,114.03	0.00	35.73
927+04.19	TO	927+54.31	0.00	0.00	723.46	-723.46	0.00	31.27	0.00	0.00	744.00	-744.00	0.00	31.01
927+54.31	TO	928+00.00	48.27	41.03	242.14	-201.11	5.31	15.48	49.13	41.76	270.16	-228.40	37.13	32.81
928+00.00	TO	929+00.00	235.28	199.99	9.87	190.12	20.91	4.57	228.07	193.86	84.39	109.47	89.04	43.63
929+00.00	TO	930+00.00	248.44	211.18	9.24	201.94	19.11	3.89	241.94	205.65	13.76	191.89	25.41	8.24
930+00.00	TO	930+54.68	127.76	108.59	8.81	99.79	15.04	4.30	124.68	105.98	15.85	90.13	25.00	8.32
936+79.42	TO	937+00.00	31.41	26.70	4.78	21.92	6.28	1.73	47.68	40.53	23.73	16.80	27.81	12.95
937+00.00	TO	938+00.00	162.70	138.30	14.00	124.30	20.83	4.91	252.06	214.25	55.46	158.78	71.56	31.33
938+00.00	TO	938+69.98	115.48	98.16	7.36	90.80	12.93	2.95	177.84	151.16	4.00	147.16	8.26	0.83
938+69.98	TO	939+00.00	23.57	20.04	1.37	18.67	3.08	0.68	70.04	59.53	1.78	57.75	3.77	0.36
939+00.00	TO	939+04.00	0.00	0.00	0.00	0.00	0.00	0.00	9.21	7.83	0.22	7.61	0.51	0.05
939+04.00	TO	940+00.00	0.00	0.00	0.00	0.00	0.00	0.00	169.49	144.07	2.54	141.53	6.08	0.57
940+00.00	TO	940+43.67	0.00	0.00	0.00	0.00	0.00	0.00	39.38	33.47	0.00	33.47	0.00	1.57
940+43.67	TO	941+00.00	0.00	0.00	0.00	0.00	0.00	0.00	30.95	26.31	0.00	26.31	0.00	2.67
941+00.00	TO	942+00.00	0.00	0.00	0.00	0.00	0.00	0.00	50.50	42.93	0.00	42.93	0.00	2.59
942+00.00	TO	943+00.00	0.00	0.00	0.00	0.00	0.00	0.00	49.41	42.00	0.00	42.00	0.00	5.35
943+00.00	TO	944+00.00	0.00	0.00	0.00	0.00	0.00	0.00	46.94	39.90	0.00	39.90	0.00	6.81

PR LINE F			STAGE 1					STAGE 2						
			EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT
STATION			(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	
904+11.64	TO	905+00.00	0.00	0.00	0.00	0.00	0.00	0.00	298.13	253.41	8.13	245.28	0.00	61.67
905+00.00	TO	906+00.00	0.00	0.00	0.00	0.00	0.00	0.00	290.43	246.86	13.83	233.03	0.00	64.48
906+00.00	TO	907+00.00	0.00	0.00	0.00	0.00	0.00	0.00	201.57	171.34	28.15	143.19	0.00	63.33
907+00.00	TO	908+00.00	0.00	0.00	0.00	0.00	0.00	0.00	144.04	122.43	56.94	65.49	0.00	70.59
908+00.00	TO	909+00.00	0.00	0.00	0.00	0.00	0.00	0.00	126.63	107.64	58.09	49.54	0.00	54.63
909+00.00	TO	909+26.74	0.00	0.00	0.00	0.00	0.00	0.00	31.75	26.98	10.98	16.00	0.00	7.97
909+26.74	TO	910+00.00	0.00	0.00	0.00	0.00	0.00	0.00	60.64	51.55	25.90	25.65	0.00	24.27
910+00.00	TO	911+00.00	0.00	0.00	0.00	0.00	0.00	0.00	52.15	44.33	32.06	12.27	0.00	41.17
911+00.00	TO	912+00.00	0.00	0.00	0.00	0.00	0.00	0.00	56.00	47.60	34.09	13.51	0.00	46.33
912+00.00	TO	913+00.00	0.00	0.00	0.00	0.00	0.00	0.00	51.37	43.66	35.59	8.07	0.00	44.50
913+00.00	TO	914+00.00	0.00	0.00	0.00	0.00	0.00	0.00	65.19	55.41	36.20	19.20	0.00	50.74
914+00.00	TO	915+00.00	0.00	0.00	0.00	0.00	0.00	0.00	84.80	72.08	32.26	39.82	0.00	55.41
915+00.00	TO	916+00.00	0.00	0.00	0.00	0.00	0.00	0.00	86.69	73.68	28.48	45.20	0.00	49.00
916+00.00	TO	917+00.00	0.00	0.00	0.00	0.00	0.00	0.00	88.06	74.85	25.28	49.57	0.00	49.48
917+00.00	TO	918+00.00	0.00	0.00	0.00	0.00	0.00	0.00	63.19	53.71	24.52	29.19	0.00	35.11
918+00.00	TO	919+00.00	0.00	0.00	0.00	0.00	0.00	0.00	39.24	33.35	25.70	7.65	0.00	20.81
919+00.00	TO	920+00.00	0.00	0.00	0.00	0.00	0.00	0.00	45.30	38.50	24.94	13.56	0.00	21.46
920+00.00	TO	921+00.00	0.00	0.00	0.00	0.00	0.00	0.00	85.54	72.71	23.06	49.65	0.00	17.02
921+00.00	TO	921+61.50	0.00	0.00	0.00	0.00	0.00	0.00	85.45	72.63	7.14	65.49	0.00	4.57

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



FILE NAME =
#FILE#

USER NAME = default
PLOT SCALE = #SCALE#
PLOT DATE = 3/29/2013

DESIGNED -
DRAWN - BC
CHECKED - RGR
DATE - 03/29/2013

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EARTHWORK SCHEDULE

SCALE: NA SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	35
CONTRACT NO. 60J12			ILLINOIS FED. AID PROJECT	

S:\1072-05-CADD\1068012-Sheet\1068012-shr-ear-theork_schedulr.dgn