

PR LINE E	STAGE 1						STAGE 2							
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
STATION	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)		
204+50.98	TO	205+00.00	35.77	30.40	0.00	30.40	0.00	0.00	21.65	18.40	0.00	18.40	0.00	0.00
205+00.00	TO	206+00.00	72.70	61.80	0.00	61.80	0.00	0.00	32.37	27.51	7.74	19.77	0.00	5.52
206+00.00	TO	207+00.00	68.87	58.54	4.65	53.89	0.00	1.93	18.63	15.84	16.41	-0.57	0.00	11.07
207+00.00	TO	208+00.00	74.54	63.36	11.11	52.25	0.00	5.46	24.80	21.08	16.04	5.04	0.00	11.11
208+00.00	TO	209+00.00	89.52	76.09	9.04	67.05	1.43	4.07	31.26	26.57	16.70	9.87	0.00	11.83
209+00.00	TO	210+00.00	110.44	93.88	6.24	87.64	17.69	6.85	36.39	30.93	17.43	13.50	0.00	12.70
210+00.00	TO	211+00.00	139.69	118.73	5.93	112.81	44.83	18.19	47.13	40.06	14.72	25.34	12.59	18.67
211+00.00	TO	212+00.00	151.28	128.59	5.28	123.31	51.67	21.30	55.41	47.10	10.61	36.49	40.31	30.85
212+00.00	TO	213+00.00	127.19	108.11	9.17	98.94	41.26	15.20	52.28	44.44	14.39	30.05	46.57	33.52
213+00.00	TO	214+00.00	104.67	88.97	240.98	-152.01	96.02	43.39	41.28	35.09	20.11	14.98	37.43	29.41
214+00.00	TO	218+31.06	0.00	0.00	4,238.58	-4,238.58	453.44	226.72	125.10	106.34	364.05	-257.71	213.16	106.58
218+31.06	TO	219+00.00	64.02	54.42	1,957.12	-1,902.70	116.53	92.81	26.55	22.57	13.09	9.49	8.91	11.85
219+00.00	TO	220+00.00	59.44	50.53	2,553.80	-2,503.27	151.69	121.56	26.30	22.87	22.87	-0.52	0.00	12.11
220+00.00	TO	221+00.00	53.89	45.81	2,190.00	-2,144.19	148.13	113.94	23.98	22.50	22.50	-2.12	0.00	12.09
221+00.00	TO	222+00.00	76.19	64.76	1,460.63	-1,395.87	167.35	124.89	32.76	27.85	15.02	12.83	0.00	9.78
222+00.00	TO	223+00.00	103.78	88.21	448.52	-360.31	93.43	85.57	44.48	37.81	9.94	27.86	6.93	10.89
223+00.00	TO	224+00.00	112.69	95.78	21.93	73.86	10.22	40.89	47.83	40.66	7.52	33.14	17.59	12.54
224+00.00	TO	224+87.94	95.17	80.90	23.87	57.02	25.00	44.85	42.10	35.78	6.71	29.07	17.13	7.80
224+87.94	TO	225+00.00	7.46	6.34	3.42	2.92	2.60	5.58	2.86	2.43	0.57	1.87	1.06	0.31
225+00.00	TO	226+00.00	24.61	20.92	23.20	-2.28	0.00	33.72	0.00	0.00	0.00	0.00	0.00	0.00
226+00.00	TO	226+45.60	13.18	11.20	5.80	5.40	0.00	7.41	0.00	0.00	0.00	0.00	0.00	0.00

PR RAMP R	STAGE 1						STAGE 2							
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
STATION	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)		
604+47.77	TO	605+00.00	23.04	19.58	19.20	0.38	0.00	8.01	0.00	0.00	0.00	0.00	0.00	0.00
605+00.00	TO	606+00.00	39.26	33.37	42.00	-8.63	0.00	17.54	0.00	0.00	0.00	0.00	0.00	0.00
606+00.00	TO	607+00.00	45.52	38.69	45.37	-6.68	0.00	20.85	0.00	0.00	0.00	0.00	0.00	0.00
607+00.00	TO	608+00.00	75.44	64.13	39.89	24.24	0.00	31.56	0.00	0.00	0.00	0.00	0.00	0.00
608+00.00	TO	609+00.00	109.26	92.87	28.09	64.78	0.00	38.59	0.00	0.00	0.00	0.00	0.00	0.00
609+00.00	TO	610+00.00	124.26	105.62	16.76	88.86	0.00	34.46	0.00	0.00	0.00	0.00	0.00	0.00
610+00.00	TO	611+00.00	119.19	101.31	17.33	83.97	6.89	33.30	0.00	0.00	0.00	0.00	0.00	0.00
611+00.00	TO	611+47.60	53.24	45.26	10.84	34.41	5.99	16.47	0.00	0.00	0.00	0.00	0.00	0.00

PR RAMP F	STAGE 1						STAGE 2							
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION	TOPSOIL PLACEMENT		
STATION	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)		
200+64.30	TO	201+00.00	0.00	0.00	0.00	0.00	0.00	0.00	49.25	41.86	8.70	33.16	7.99	16.47
201+00.00	TO	202+00.00	62.59	53.20	2.20	51.00	20.94	4.52	97.52	82.89	7.31	75.58	28.33	40.61
202+00.00	TO	203+00.00	132.78	112.86	159.39	-46.53	115.28	34.98	57.63	48.99	2.20	46.78	15.26	39.04
203+00.00	TO	204+00.00	129.37	109.96	405.11	-295.15	200.87	67.56	42.61	36.22	15.02	21.20	46.09	56.07
204+00.00	TO	205+00.00	123.15	104.68	547.17	-442.49	222.96	80.54	32.31	27.47	17.50	9.97	53.30	58.69
205+00.00	TO	206+00.00	137.33	116.73	609.76	-493.03	234.43	86.56	49.20	41.82	6.37	35.45	39.74	48.28
206+00.00	TO	207+00.00	137.37	116.76	678.81	-562.05	238.81	88.87	59.80	50.83	4.63	46.20	54.61	49.87
207+00.00	TO	208+00.00	114.94	97.70	734.63	-636.93	244.57	92.93	70.67	60.07	4.31	55.75	35.63	34.50
208+00.00	TO	209+00.00	91.72	77.96	683.48	-605.52	235.54	89.54	74.44	63.28	3.70	59.57	13.31	18.89
209+00.00	TO	210+00.00	95.22	80.94	559.69	-478.75	213.87	84.74	58.80	49.98	4.96	45.01	18.93	17.41
210+00.00	TO	211+00.00	140.87	119.74	256.28	-136.54	120.37	49.31	42.80	36.38	3.59	32.78	9.85	7.81
211+00.00	TO	211+31.24	53.09	45.13	7.80	37.33	8.00	4.21	10.49	8.92	0.00	8.92	0.00	0.00

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312.228.0100  
www.bbainc.com



FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
#FILE#		DRAWN - BC	REVISED -
		CHECKED - RGR	REVISED -
		DATE - 03/29/2013	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EARTHWORK SCHEDULE

SCALE: NA SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2012-059-BR	COOK	631	36
CONTRACT NO. 60J12			ILLINOIS FED. AID PROJECT	

S:\1072-05-CADD\0160J12-Sht-rtr-thwork\_sched.dgn