SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005 QUANTITY (100% STATE)	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23	
40600300	AGGREGATE (PRIME COAT)	TON	177	177	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1620	1620	1
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	90	90	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	245	245	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3300	3300	1
1 44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	29,465	29,465	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,415	1,415	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	100	100	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	650	650	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100	100	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	350	350	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,485	1,485	

* INDICATES SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0005 QUANTITY (100% STATE)	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	7	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	LSUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	LSUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,403	5,403	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	61,406	61,406	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	96	96	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	601	601	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	30,703	30,703	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	48	48	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	248	248	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	7	7	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	248	248	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1	

* INDICATES SPECIALTY ITEM

1 Rev. 6-5-13

DESIGNED - TMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 23 POPLAR ROAD TO INTERSTATE 90 SUMMARY OF QUANTITIES
DRAWN - BCD	REVISED -		
CHECKED - RWL	REVISED -		
DATE - 12-12-10	FILE - 100153-W015-S00.sht		SCALE: NONE STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
324	24-RS-4	McHENRY	16	3
		CONTRACT NO. 60N34		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

COPYRIGHT © 2010 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001201 - EXPIRES 4/30/2011
10/27/2010 14:40:17 AM