SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0014
				0014
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	12770	12770
X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	85	85
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	125	125
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ YD	41	41
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	17	17
Z0006014	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	885	885
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	885	885
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	50	50
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	2	2
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	11	11

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0014
				0014
~~Z0016200~~	~~DECK SLAB REPAIR (PARTIAL)~~	~~SQ YD~~	~~47~~	~~47~~
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4
1/2				
~~30300104~~	~~AGGREGATE SUBGRADE IMPROVEMENT, 4"~~	~~SQ YD~~	~~230~~	~~230~~
31101200	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	188	188
42001300	PROTECTIVE COAT	SQ YD	231	231
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	237	237
44003100	MEDIAN REMOVAL	SQ FT	1686	1686
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	237	237
60618320	CONCRETE MEDIAN SURFACE, 6"	SQ FT	1686	1686
Z0062456	TEMPORARY PAVEMENT	SQ YD	230	230

△1 △1 △1 Rev. 6-3-13 Rev.

FILE NAME =	USER NAME = gorengautab	DESIGNED -	REVISED -
c:\pw_work\pwidot\gorengautab\d027315\D162311-sht-plan.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	2011-067-1	DUPAGE	29	4
		CONTRACT NO. 60P86		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

D162311-sht-plan.dgn 12/14/2012 10:14:50 AM User=gorengautab