

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE ROADWAY				
44201299	DOWEL BARS 1 1/2"	EACH	911	911				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	211	211				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	594	594				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	1000	1000				
44213100	PAVEMENT FABRIC	SO YD	1767	1767				
44213200	SAW CUTS	FOOT	868	868				
44213204	TIE BARS 3/4"	EACH	826	826				
60360100	INLETS TO BE ADJUSTED	EACH	233	233				
60266600	VALVE BOXES TO BE ADJUSTED	EACH	85	85				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	51	51				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	100	100				
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	15	15				
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	15	15				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE ROADWAY				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	38000	38000				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	1857.6	1857.6				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	81134	81134				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4681	4681				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1352	1352				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	14471	14471				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2587	2587				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1857.6	1857.6				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	81134	81134				

* SPECIALTY ITEMS

FILE NAME :	USER NAME : jbruceh	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WESTERN AVENUE (34TH STREET TO COLUMBUS DRIVE) SUMMARY OF QUANTITIES	F.A.P. RTE. :	SECTION :	COUNTY :	TOTAL SHEETS :	SHEET NO. :
PLT SCALE : 100/2000 1/4"	CHECKED -	REVISED -	370			2011-089-RS	COOK	30	4	
PLT DATE : 4/11/2013	DATE -	REVISED -	CONTRACT NO. 60R16							
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.