

90% FEDERAL 10% STATE

90% FEDERAL 10% STATE

			URBAN	CONSTRUCTION CODE 0021
			79TH STREET AT STATE ROAD	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3733	3733
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	149	149
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	996	996
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	4	4
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2	2
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1	1
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1	1
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1	1
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24	24
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	33.5	33.5
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	11	11
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6	6
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4	4
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4	4
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6	6
88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10	10

			URBAN	CONSTRUCTION CODE 0021
			79TH STREET AT STATE ROAD	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
88500100	INDUCTIVE LOOP DETECTOR	EACH	10	10
88600100	DETECTOR LOOP, TYPE I	FOOT	693	693
88800100	PEDESTRIAN PUSH-BUTTON	EACH	10	10
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1
89502380	REMOVE EXISTING HANDHOLE	EACH	16	16
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	12	12
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1272	1272
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1
X4402805	ISLAND REMOVAL	SQ. FT	672	672
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	1
X8620200	UNINTERRUPTIBLE POWER SUPPLY, SPECIAL	EACH	1	1
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	1040	1040
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	25.7	25.7
Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1	1
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1
0 Z0076600	TRAINEES	HOUR	500	500
0 Z0076604	TRAINEES-TRAINING PROGRAM GRADUATE	HOUR	500	500
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	100	100
* 66900400	SPECIAL WASTE GROUND WATER DISPOSAL	GAL	200	200
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4

\* Specialty Hems @ 0042

FILE NAME * MICROST\352104\ 84-SUMMARY.DGN	USER NAME * JGC	DESIGNED - KK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES 79TH STREET @ STATE ROAD				F.A.U. RTE. 1548	SECTION (461-Y) TS	COUNTY COOK	TOTAL SHEETS 24	SHEET NO. 4			
	PLOT SCALE * 1"=20'	DRAWN - RDS/JGC	REVISED -					SCALE: 1"=20'				SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60T94		
	PLOT DATE * 12-6-12	CHECKED - BPT	REVISED -																
		DATE - 12-6-12	REVISED -																