


90% FED. / 10% STATE  
URBAN

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0021 TRAFFIC SIGNALS			
				IL ROUTE 19/ FOREST PRESERVE /OCTAVIA	IL ROUTE 19/ IL ROUTE 43	IL ROUTE 43/ FOREST PRESERVE	INTERCONNECT
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	760	412	150	198	
42001300	PROTECTIVE COAT	SQ YD	868	431	190	247	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	5600	2475	1350	1775	
42400800	DETECTABLE WARNINGS	SQ FT	395	186	90	119	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	676	355	142	179	
44000600	SIDEWALK REMOVAL	SQ FT	5600	2475	1350	1775	
44003100	MEDIAN REMOVAL	SQ FT	1044	1044			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	676	355	142	179	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	399	399			
60624600	CORRUGATED MEDIAN	SQ FT	564	564			
67100100	MOBILIZATION	L SUM	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1				
* 72000200	SIGN PANEL - TYPE 2	SQ FT	166	58	60	48	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	420	420			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2182	1077	346	759	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	34	34			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	44	44			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	251	52	199		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1821	888	561	372	
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	3	1	1	1	
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	3108	719	656	893	840
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	221	88	52	81	
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	140	39	48	53	
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1783	935	372	476	
81400100	HANDHOLE	EACH	15	6	4	4	1
81400200	HEAVY-DUTY HANDHOLE	EACH	13	5	4	4	
81400300	DOUBLE HANDHOLE	EACH	8	4	2	2	

\* 60900200 NON-SPECIAL WASTE DISPOSAL CUYD 110 37 30 37  
 \* 60900400 SPECIAL WASTE GROUNDWATER DISPOSAL GAL 1850 617 616 617  
 \* 60900450 SPECIAL WASTE PLANS AND REPORTS L SUM 1 0.34 0.33 0.33  
 \* 60900530 SOIL DISPOSAL ANALYSIS EACH 4 2 1 1

\*Specialty Items Rev.

	USER NAME = jmh	DESIGNED - BRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 0348	SECTION 2012-041TS	COUNTY COOK	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 40,0000 1" = 100'	DRAWN - MFB	REVISED -		IL ROUTE 19 (IRVING PARK RD.) / IL ROUTE 43 (HARLEM AV.) FOREST PRESERVE DRIVE						34	3
	PLOT DATE = 3/28/2013	CHECKED - JJE	REVISED -		NO SCALE SHEET NO. 1 OF 3 SHEETS STA. TO STA.						CONTRACT NO. 60197	
	DATE - 03/21/2013	REVISED -		ILLINOIS FED. AID PROJECT								