

URBAN  
90% FED.  
10% STATE

SUMMARY OF QUANTITIES				LOCATION OF WORK	IL 59 AT MAIN STREET	IL 59 AT WASHINGTON STREET	INTERCONNECT	
				FUNDING BREAKDOWNS				
				TYPE		TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT
CODE NO.	ITEM	UNIT	TOTAL	URBAN 0021	URBAN 0021	URBAN 0021	URBAN 0042	
20200100	EARTH EXCAVATION	CU YD	5		5			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1,625	565	1,060			
42400800	DETECTABLE WARNINGS	SO FT	196	100	96			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	345	200	145			
44000600	SIDEWALK REMOVAL	SO FT	1,520	565	955			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4	3	1			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	116	116				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	84	84				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	1	1		
67100100	MOBILIZATION	L SUM	1	0.40	0.40	0.20		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.50	0.50			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.40	0.40	0.20		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.40	0.40	0.20		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.40	0.40	0.20		

\* 66900200 NON-SPECIAL WASTE DISPOSAL CU YD 10 10  
 \* 66900450 SPECIAL WASTE PLANS AND REPORTS L SUM 1 1  
 \* 66900530 SOIL DISPOSAL ANALYSIS EACH 1 1