URBAN
90% FED/10% STATE

	CODE NO.	ITEM	UNIT	TOTAL	IL 59 AT MAIN STREET	IL 59 AT WASHINGTON STREET	INTERCONNECT	
		SUMMARY OF QUANTITIES	LOCATION OF WORK					
			FUNDING BREAKDOWNS					
			TYPE		TRAFFIC SIGNALS URBAN	TRAFFIC SIGNALS URBAN	INTERCONNECT URBAN	URBAN
					0021	0021	0021	0042
**	72000100	SIGN PANEL - TYPE 1	SQ FT	33	12	21		
**	72000200	SIGN PANEL - TYPE 2	SQ FT	105	35	70		
**	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,210	570	640		
**	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	20		20		
**	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	260	250	10		
**	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	293	149	144		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,000	534	466		
	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2	1	1		
	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	742	205	433	104	
	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	124	66	58		
	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	117	40	77		
	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	882	388	494		
	81400100	HANDHOLE	EACH	6	2	4		
	81400200	HEAVY-DUTY HANDHOLE	EACH	8	4	4		

** SPECIALTY ITEMS

GHA #4085.884

FILE NAME = 60V59-1504.dgn	USER NAME = jwoulfe	DESIGNED - JOR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 2 OF 6)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JPW	REVISED -			338	2012-056TS	DuPAGE	32	4
Default	PLOT SCALE = 1:20	CHECKED - KLB	REVISED -		SCALE: NONE SHEET ___ OF ___ SHEETS STA. ___ TO STA. ___			CONTRACT NO. 60V59		
	PLOT DATE = 3/22/2013	DATE -	REVISED -				ILLINOIS FED. AID PROJECT			