

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																					
				TRAFFIC SIGNAL																					
				0021 URBAN																					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22				
X8803040	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	6	4																		2			
X8803051	SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION, 1-5 SECTION, BRACKET MOUNTED, RETROFIT	EACH	1	1																					
X8803060	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	1	1																					
X8803082	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	16	1		2	3			4	2		2									4			
X8803084	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	49	10		6	3			2	6		8				6		8			8			
X8803088	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	19	6		2	1			2	2		2				2		2			4			
X8803090	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	3				1															2			
X8803120	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED, RETROFIT	EACH	3	3																					
X8803210	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED, RETROFIT	EACH	12	1		2	1			2	2						2		2						
X8803910	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED RETROFIT	EACH	2							2															
X8880015	PEDESTRIAN PUSH-BUTTON, NON-LATCHING	EACH	50	11					6		4		13	4	4	4					4				
<input type="checkbox"/>	20070604 TRAINEES-TRAINING PROGRAM GRADUATE	HOUR	500	500																					

# 0042

FILE NAME	USER NAME	DESIGNED	REVISED
cd:\pwork\pwork\rosadovazquez\08335	rosadovazquez	-	-
	79\0121713-sh1-TS.dgn	DRAWN	REVISED
		-	-
	PLOT SCALE = 40:2000 1/4" = 1'	CHECKED	REVISED
		-	-
#MODELNAME	PLOT DATE = 3/29/2013	DATE	REVISED
		-	-

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES (SHEET 4 OF 4)			
SCALE:	SHEET	OF	SHEETS
	STA.	TO	STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	2013-004-1	WILL	58	8
CONTRACT NO. 60W22			ILLINOIS FED. AID PROJECT	

Rev.