

| CODE NO.   | ITEM  | UNIT  | TOTAL QUANTITY | CONSTR. CODE  |         |
|------------|---|-------|----------------|---------------|---------|
|            |   |       |                | URBAN ROADWAY | UTILITY |
|            |   |       |                | 0004          | 0043    |
| 40601005   | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES        | TON   | 20             | 20            |         |
| 42400200   | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH        | SQ FT | 100            | 100           |         |
| 44002215   | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4"    | SQ YD | 96             | 96            |         |
| 44201347   | CLASS C PATCHES, TYPE IV, 9 INCH                | SQ YD | 96             | 96            |         |
| 67100100   | MOBILIZATION                                    | LSUM  | 1              | 1             |         |
| 70301000   | WORK ZONE PAVEMENT MARKING REMOVAL              | SQ FT | 2175           | 2175          |         |
| • 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4"        | FOOT  | 500            | 500           |         |
| • 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24"       | FOOT  | 50             | 50            |         |
| X7010216   | TRAFFIC CONTROL AND PROTECTION, (SPECIAL)       | LSUM  | 1              | 1             |         |
| X7011015   | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)    | LSUM  | 1              | 1             |         |
| X7030030   | WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH  | FOOT  | 6465           | 6465          |         |
| X7030055   | WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH | FOOT  | 20             | 20            |         |
| Z0030850   | TEMPORARY INFORMATION SIGNING                   | SQ FT | 154            | 154           |         |
| X0327598   | LOCATE TUNNEL                                   | LSUM  | 1              | 1             |         |

14

• - DENOTES SPECIALTY ITEM

|             |                             |            |           |   |                              |       |    |        |             |               |        |                           |           |
|-------------|-----------------------------|------------|-----------|---|------------------------------|-------|----|--------|-------------|---------------|--------|---------------------------|-----------|
| FILE NAME : | USER NAME : rgal            | DESIGNED - | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> |       |    |        | F.A.I. RTE. | SECTION       | COUNTY | TOTAL SHEETS              | SHEET NO. |
|             | PLOT SCALE : 100.0000' / 1" | DRAWN -    | REVISED - |   |                              |       |    |        | 90/94       | 0101.6-2P-1-3 | COOK   | 37                        | 3         |
|             | PLOT DATE : 4/12/2013       | CHECKED -  | REVISED - |   | SCALE:                       | SHEET | OF | SHEETS | STA.        | TO            | STA.   | ILLINOIS FED. AID PROJECT |           |
|             |                             | DATE -     | REVISED - |   |                              |       |    |        |             |               |        | CONTRACT NO. 60W36        |           |