

FUNDS: 80% FEDERAL (HBP), 20% LOCAL
CONSTRUCTION TYPE CODE 0014

PAY CODE	DESCRIPTION	UNIT	TOTAL QUANTITY
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	43
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	94
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2
60236200	INLETS, TYPE A, TYPE 3 GRATE	EACH	1
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1
60500050	REMOVING CATCH BASINS	EACH	1
60600605	CONCRETE CURB, TYPE B	FOOT	47
60603600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	482
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	29
67100100	MOBILIZATION	L SUM	1
* K0012960	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	1
*** X0426200	DEWATERING	L SUM	1
*** X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	55
*** X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1
*** X5021510	COFFERDAMS (SPECIAL)	EACH	2
*** X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	228
*** * X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
*** Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	65

FUNDS: 80% FEDERAL (HBP), 20% LOCAL
CONSTRUCTION TYPE CODE 0014

PAY CODE	DESCRIPTION	UNIT	TOTAL QUANTITY
Z0013796	CONSTRUCTION LAYOUT	L SUM	1
*** Z0016600	DUST CONTROL WATERING	UNIT	10
*** ** Z0076600	TRAINEES	HOUR	500
*** ** Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500
* SPECIALTY ITEMS ** CONSTRUCTION TYPE CODE 0042 *** SPECIAL PROVISION REQUIRED			

FILE NAME =
N:\P\1106\6012\501012\1011\00110012.02.dwg

USER NAME = jprozier
PLOT SCALE = 20'
PLOT DATE = 2/12/2013

DESIGNED - JA
DRAWN - PDR
CHECKED - JCS
DATE - 11/30/12

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CARRIAGE WAY DRIVE
SUMMARY OF QUANTITIES
SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
10-00101-00-BR		COOK	34	4

CONTRACT NO. 63787
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT