

SUMMARY OF QUANTITIES

SPECIAL PROVISION SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%		
					COUNTY = 20%		
					ROADWAY	TRAFFIC SIGNALS	TRAINEES
					0004	0021	0042
	20100210	TREE REMOVAL (OVER 16 UNITS DIAMETER)	UNIT	34	34		
Δ	20200100	EARTH EXCAVATION	CU YD	2,470	2,470		
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	514	514		
	20800150	TRENCH BACKFILL	CU YD	107	107		
	21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,850	1,850		
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7,200	7,200		
	21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	200	200		
*	25000210	SEEDING, CLASS 2A	ACRE	0.85	0.85		
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	118	118		
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	118	118		
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	118	118		
*	25100630	EROSION CONTROL BLANKET	SQ YD	3,982	3,982		
*	25100900	TURF REINFORCEMENT MAT	SQ YD	43	43		
*	25200110	SODDING, SALT TOLERANT	SQ YD	3,238	3,238		
*	25200200	SUPPLEMENTAL WATERING	UNIT	30	30		
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	150		
	28000305	TEMPORARY DITCH CHECKS	FOOT	96	96		
	28000400	PERIMETER EROSION BARRIER	FOOT	4,037	4,037		
	28000500	INLET AND PIPE PROTECTION	EACH	14	14		
	28000510	INLET FILTERS	EACH	23	23		
Δ	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	514	514		
Δ	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	3,311	3,311		
	35501315	HOT-MIX ASPHALT BASE COURSE, 7 3/4"	SQ YD	1,758	1,758		
Δ	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	500	500		
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,301	3,301		
	40600300	AGGREGATE (PRIME COAT)	TON	50	50		
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	418	418		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	245	245		
	40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1,465	1,465		
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1,237	1,237		
Δ	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	50	50		
	42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	40	40		
	42001300	PROTECTIVE COAT	SQ YD	1,131	1,131		
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31	31		
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	972	972		
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	704	704		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,734	3,734		
	44000600	SIDEWALK REMOVAL	SQ FT	375	375		
	44201835	CLASS D PATCHES, TYPE I, 16 INCH	SQ YD	28	28		
	44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	5	5		

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEM

SPECIAL PROVISION SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%		
					COUNTY = 20%		
					ROADWAY	TRAFFIC SIGNALS	TRAINEES
					0004	0021	0042
	44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	174	174		
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	7	7		
	50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1		
	50105220	PIPE CULVERT REMOVAL	FOOT	158	158		
	54200220	PIPE CULVERTS, CLASS D, TYPE 1 16"	FOOT	149	149		
	54215550	METAL END SECTIONS 15"	EACH	6	6		
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	207	207		
	550A0070	STORM SEWERS, CLASS A, TYPE 1 16"	FOOT	83	83		
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	793	793		
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	191	191		
	55100300	STORM SEWER REMOVAL 12"	FOOT	630	630		
Δ *	55400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	2	2		
	60107700	PIPE UNDERDRAINS 6"	FOOT	40	40		
	60201110	CATCH BASINS, TYPE A, 4-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	1	1		
	60201340	CATCH BASINS, TYPE A, 4-DIAMETER, TYPE 24-FRAME AND GRATE	EACH	11	11		
	60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	1	1		
	60208240	CATCH BASINS, TYPE C, TYPE 24-FRAME AND GRATE	EACH	9	9		
	60218400	MANHOLES, TYPE A, 4-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8		
	60219000	MANHOLES, TYPE A, 4-DIAMETER, TYPE 8 GRATE	EACH	1	1		
	60221100	MANHOLES, TYPE A, 5-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1		
	60255500	MANHOLES TO BE ADJUSTED	EACH	1	1		
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2		
	60280100	INLETS TO BE ADJUSTED	EACH	6	6		
	60282700	INLETS TO BE RECONSTRUCTED	EACH	1	1		
	60283000	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2		
	60286100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	1	1		
Δ	60286800	VALVE BOXES TO BE ADJUSTED	EACH	4	4		
	60500040	REMOVING MANHOLES	EACH	1	1		
	60500050	REMOVING CATCH BASINS	EACH	1	1		
	60500060	REMOVING INLETS	EACH	10	10		
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	40	40		
	60608000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3,755	3,755		
	67100100	MOBILIZATION	L SUM	1	1		
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4		
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,796	1,796		
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14,954	14,954		
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	90	90		
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1,750	1,750		
	70300580	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	180	180		

Pc11ted:2/18/2013 7:09:55 AM By:JSchmidt

**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60054  
830.406.6700 / www.eeinc.com

**KANE COUNTY DIVISION  
OF TRANSPORTATION**  
41W011 BURLINGTON ROAD  
ST. CHARLES, IL 60175

DESIGNED TVW, SWM	REVISED JPS 02/04/13
DRAWN JPS	REVISED -
CHECKED JRL	REVISED -
DATE 12/7/12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**FABYAN PARKWAY  
SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE. 363	SECTION 10-00404-00-CH C-91-496-10	COUNTY KANE	TOTAL SHEET SHEETS NO. 59 4
CONTRACT NO. 63818			ILLINOIS FED. AID PROJECT CMM-90036271